



MNR University

[Established under the Telangana State Private Universities

(Establishment and Regulation) (Amendment) Act No. 11 of 2024]

MNR Nagar, Fasalwadi, Sangareddy District, Gr. Hyderabad – 502294

MNRU School of Engineering & Technology and Artificial Intelligence

A.Y. : 2025-26

B.Tech I Year - II Semester

25CSE104 - Software Crafting & Sculpting Lab

Name of the Student: K.BISHWAS

Program: B.Tech (Hons.) CSE/CSE (AI&ML)/ CSE (AI&DS)

Section: A

Hall Ticket Number: 25RBAIM0016

Index

S. No.	Name of the Exercise
1	Development of Problem Statement.
2	Preparation of Software Requirement Specification (SRS) Document, Design Documents, and Testing Phase related documents.
3	Preparation of Software Configuration Management (SCM) and Risk Management related documents.
4	Study and usage of any Design Phase CASE tool.
5	Preparation and Development of an ER Diagram for a given problem statement using any Design Phase CASE tool.
6	Preparation and Development of Data Flow Diagrams (DFD) including Context Diagram, Level 0 DFD, and Level 1 DFD for a given system using any Design Phase CASE tool.
7	Performing the Structural Design using any Design Phase CASE tool.
8	Performing the Behavioral Design using any Design Phase CASE tool.
9	Study and usage of any Software Testing Tool for performing Functional and/or Automated Testing on a given application. (Selenium, JUnit, TestNG, JMeter, Postman, etc.)
10	Develop test cases for Unit Testing and Integration Testing.
11	Develop test cases for various White Box and Black Box Testing techniques.
12	Develop a Mini Software Engineering case study and prototype design for a modern application

TASK 01 : DEVELOPMENT OF PROBLEM STATEMENT

PHASE 1: CONTEXTUAL BACKGROUND:

Modern global infrastructure, comprising communications, navigation with forecasting, and Earth observation, relies heavily on the orbital environment. However, the rapid commercialization of space and the development of mega-constellations have led to an exponential increase in satellite launches. Earth's orbit is becoming increasingly congested with nonfunctional spacecraft, spent rocket stages, and fragmentation debris.

PHASE 2: THE CORE PROBLEM:

There are currently over 36,000 tracked objects larger than 10 cm in orbit, with estimates of more than 1 million objects between 1 cm and 10 cm, and hundreds of millions of smaller particles. Even sub-centimeter debris poses a catastrophic threat due to orbital velocities exceeding 7 km/s. The core problem is the looming risk of Kessler syndrome, a cascading chain reaction in which collisions create more debris, making certain orbital altitudes unusable for generations.

PHASE 3: IDENTIFYING THE GAPS:

To formulate a strong problem statement, we must identify the specific technological and systematic gaps.

1. TRACKING LIMITATIONS:

- Current ground-based radar and optical systems struggle to track objects smaller than 10 cm with high accuracy.
- Tracking in high-altitude orbits is less capable than tracking in low orbit.
- There is a lack of real-time, continuous global coverage.
- Tracking is often inhibited by weather, daylight, and geographic gaps.

2. MITIGATION LIMITATIONS:

- There is no scalable, operational system for active debris removal.

- Rendezvous with non-cooperative, tumbling debris remains technologically immature.
- There is a lack of standardized global policies and economic incentives for satellite operators to deorbit satellites.

PHASE 4:THE CONSEQUENCES(THE MPACT OF INACTION):

If unaddressed, the loss of key orbital shells will degrade critical satellite services, incur billions of dollars in infrastructure losses, and pose an extreme hazard to human spaceflight.

PHASE 5: THE SYNTHESIZED PROBLEM STATEMENTS:

1. **COMPREHENSIVE:** The rapid accumulation of space debris in Earth's orbit poses an escalating and existential threat to operational spacecraft, human spaceflight, and the future viability of the orbit economy. Despite growing awareness of the current space situation, systems lack the resolution, coverage, and real-time capabilities to accurately track debris smaller than 10 cm. Meanwhile, technologies to reduce them remain technologically immature and economically unscalable. Without an integrated framework for precise tracking, autonomous collision avoidance, and effective de-orbit remediation, the risk of cascading collisions will render orbital regimes permanently unusable.
2. **TRACKING-FOCUSED:** The safety of operational spacecraft is severely compromised by the inability of current ground-based tracking systems to accurately detect, track, and predict the trajectories of small debris or orbital debris, which comprise the vast majority of collisional threats. This tracking defect results in unreliable collision warnings. There is a critical need for advanced sensor fusion and predictive algorithms to provide high-fidelity real-time space situational awareness to prevent catastrophic collisions.
3. **MITIGATION-FOCUSED:**As defunct satellites and spent rocket stages accumulate in orbit, they serve as primary catalysts for further cascading generations of space debris. Current mitigation strategies rely heavily on voluntary de-orbiting guidelines, which are frequently unenforced, while technological solutions for active debris removal remain largely experimental. There is a critical need for the development of robust, cost-effective ADR technology refers to systems capable of autonomous windowizing and of developing non-cooperative, tumbling targets to remediate the existing diverse population and secure the orbital environment.

Task 02: PREPARATION OF SOFTWARE REQUIREMENT SPECIFICATION DOCUMENT, DESIGN DOCUMENT AND TESTING PHASE RELATED DOCUMENTS

PART A: SOFTWARE REQUIREMENTS SPECIFICATION (SRS) DOCUMENT

Document ID: SRS-SDTMS-001 Version: 1.0 System Name: OrbitGuard (Space Debris Tracking and Mitigation System)

1. Introduction

1.1 Purpose

The purpose of this document is to define the complete software requirements for the OrbitGuard system. It details the functional, non-functional, and interface requirements necessary to track orbital debris, predict conjunctions (collisions), and manage Active Debris Removal (ADR) mission planning.

1.2 Scope

OrbitGuard will ingest telemetry and tracking data from ground-based sensors and space surveillance networks, process orbital trajectories, calculate collision probabilities, and provide a decision-support system for mitigation and ADR operations.

2. Overall Description

2.1 User Characteristics

- Orbital Analysts: Monitor debris trajectories, refine orbital models, and assess collision risks.
- Mission Planners: Plan and simulate Active Debris Removal (ADR) missions.
- System Administrators: Manage data feeds, user access, and system health.

3. Specific Requirements

3.1 Functional Requirements

- FR-01: Data Ingestion: The system shall ingest Two-Line Element (TLE) sets, radar, and optical tracking data from external sources (e.g., Space-Track.org, commercial sensors) at intervals of no more than 5 minutes.

- FR-02: Orbit Propagation: The system shall calculate and predict the future trajectories of tracked objects using standard models (e.g., SGP4/SDP4) for a minimum of 30 days.
- FR-03: Conjunction Assessment: The system shall automatically identify close approaches between tracked objects and calculate the Probability of Collision (Pc) using Monte Carlo or covariance-based methods.
- FR-04: Alert Generation: The system shall generate high-priority alerts when the Probability of Collision exceeds $1e-4$ (0.0001).
- FR-05: ADR Mission Simulation: The system shall allow Mission Planners to input ADR spacecraft parameters and simulate rendezvous trajectories with non-cooperative, tumbling debris.
- FR-06: Visualization: The system shall render a 3D real-time visualization of Earth's orbit, displaying active satellites and debris clusters (GEO and LEO).

3.2 Non-Functional Requirements

- NFR-01: Performance: Orbit propagation calculations for up to 50,000 objects must be processed within 10 minutes of new data ingestion.
- NFR-02: Availability: The system shall maintain 99.99% uptime, as missed tracking data could result in catastrophic collisions.
- NFR-03: Security: All external data feeds must be validated and sanitized to prevent injection attacks. Role-Based Access Control (RBAC) must be enforced.
- NFR-04: Scalability: The system architecture shall support scaling to 500,000 tracked objects without degradation in computation time.

3.3 External Interface Requirements

- API Interfaces: RESTful APIs for pulling data from 18th Space Defense Squadron (18 SDS) and commercial providers.
- UI Interfaces: Web-based dashboard compatible with Chrome, Firefox, and Edge.

PART B: SOFTWARE DESIGN DOCUMENT (SDD)

Document ID: SDD-SDTMS-001 Version: 1.0

1. Introduction

This document outlines the architectural and detailed design of the OrbitGuard system, translating the SRS into a technical blueprint.

2. System Architecture Design

The system follows a Microservices Architecture to ensure scalability and independent deployment of tracking, processing, and mitigation modules.

2.1 High-Level Components

1. Data Ingestion Service: Pulls TLEs and raw sensor data via APIs.
2. Orbit Propagation Engine: High-performance computing module (C++/Python) calculating trajectories.
3. Conjunction Assessment Module: Calculates P_c for all pairs.
4. ADR Mission Simulator: Physics engine for planning debris capture.
5. Web UI & API Gateway: User-facing dashboard and visualization (Three.js/WebGL).

3. Data Design

3.1 Database Selection

- Time-Series Database (InfluxDB): Stores historical tracking data and telemetry.
- Relational Database (PostgreSQL): Stores object metadata (launch date, mass, size, owner).
- NoSQL (Redis): Caching for real-time 3D rendering coordinates.

3.2 Key Data Structures

- Object_State_Table: [**Object_ID, Epoch, Inclination, RAAN, Eccentricity, Arg_Perigee, Mean_Anomaly, Mean_Motion**]
- Conjunction_Event_Table: [**Event_ID, Object_1_ID, Object_2_ID, TCA (Time of Closest Approach), Miss_Distance, P_c**]

4. Component Detailed Design (Example: Conjunction Assessment Module)

- Input: Propagated ephemeris of all active satellites and tracked debris.
- Process:
 1. *Geometric Filter*: Discard pairs with a maximum possible intersection distance > 10 km.
 2. *Time Filter*: Calculate Time of Closest Approach (TCA).
 3. *Probability Calculation*: Compute combined covariance matrix and calculate P_c .

- Output: Conjunction Data Messages (CDMs) pushed to the Alert Service and UI.

PART C: TESTING PHASE RELATED DOCUMENTS

To ensure the Orbit Guard system is reliable, three critical testing documents are prepared: Test Plan, Test Cases, and a Defect Report template.

DOCUMENT 1: TEST PLAN

Document ID: TP-SDTMS-001

1. Scope of Testing

Testing will cover the Data Ingestion, Orbit Propagation, Conjunction Assessment, and ADR Simulation modules.

2. Testing Types

- Unit Testing: Individual functions (e.g., SGP4 propagator calculations) tested via automated scripts (PyTest).
- Integration Testing: Verification that the Data Ingestion Service correctly passes formatted data to the Propagation Engine.
- Performance Testing: Simulate ingesting 50,000 TLEs and measure processing time against the 10-minute NFR.
- Security Testing: Penetration testing on API endpoints and RBAC validation.

3. Test Environment

- Hardware: Cloud-based AWS EC2 instances (GPU-optimized for 3D rendering testing, Compute-optimized for propagation).
- Software: Ubuntu 22.04, Docker, Kubernetes.

4. Entry/Exit Criteria

- Entry: Software build is successfully compiled and unit-tested with 0 critical bugs.
- Exit: 100% of high-priority test cases pass, and no critical/high severity defects remain open.

TEST CASE ID	MODULE	TEST SCENARIO	PRE-CONDITIONS	TEST STEPS	EXPECTED RESULT	PRIORITY
TC-001	Data Ingestion	Verify ingestion of	Data Ingestion	1.Trigger TLE pul	TLE data is parsed and	High

		valid TLE data	Service is running; Space-Track API is accessible Thank you.	form Space-Track. 2.Check Database	stored in Postgre SQL with correct Epoch time	
TC-002	Conjunction	Verify alert generation for high PC	Propagation Engine has run; Test data includes two objects on collision course	1.Inject simulated collisions trajectory data. 2.wait for CA Module to run.	Alert is generated within 2 minutes; PC calculated $>1e-4$; UI displays red warning.	Critical
TC-003	Visualization	Verify 3D rendering of LEO debris	UI is loaded; redis cache has orbital coordinates	1.Open Dashboard. 2.Navigate to LEO view	Debris points render without lag; FPS > 30 .	Medium
TC-004	ADR Sim	Simulate rendezvous with tumbling debris	ADR Mission Simulator is active	1.Input tumble rate of 5 deg/s for target. 2.Run simulation	Simulator calculates correct delta-V required for match; no physics engine crashes.	High
TC-005	Security	Verify unauthorized access is blocked	Standard user account credentials	1. Attempt to access Admin-level ADR simulation API endpoint.	System returns HTTP 403 Forbidden.	Critical

DOCUMENT 3: DEFECT REPORT TEMPLATE

When a test case fails, the QA engineer logs a defect using the following structure.

FIELD	DESCRIPTION / EXAMPLE ENTRY
DEFECT ID	BUG-SDTMS-0042
TEST CASE ID	TC-002
SUMMARY	Conjunction Alert not generated for $P_c > 1e-4$ during High load
SEVERITY	Critical
PRIORITY	P1
ENVIRONMENT	AWS EC2 c5.4xLarge,Ubuntu 22.04, Build #1.0.4
DESCRIPTION	When ingesting a batch of > 30000 TLEs, the Conjunction Assessment ? Module skips Calculating P_c for objects with an eccentricity > 0.6 therefore, no alert was generated for the injected collisions data.
STEPS TO REPRODUCE	1.Ingest full 30k TLE dataset. 2.Inject high-eccentricity collision data($e=0.75$). 3.Observe CA Module logs.
EXPECTED RESULT	P_c is calculated and Alert is generated regardless of eccentricity.
ACTUAL RESULT	Calculating skipped; no alert generated. Log shows “Invalid orbit type filter applied”.
ASSIGNED TO	Lead Orbital Mechanics Developer

STATUS	Open
--------	------

TASK 03: SOFTWARE CONFIGURATION MANAGEMENT AND RISK MANAGEMENT RELATED DOCUMENTS

1. Introduction

1.1 Purpose

The purpose of this SCM Plan is to define the activities, tools, and processes used to identify, control, and track the configurations of the OrbitGuard software, documentation, and environments throughout the project lifecycle.

1.2 Scope

This plan covers all configuration items (CIs) including source code (propagation engines, UI, APIs), test scripts, infrastructure-as-code, and project documentation (SRS, SDD, etc.).

2. Configuration Management Organization & Responsibilities

- Configuration Manager: Owns the SCM process, manages the main branch, and enforces the change control process.
- Development Team: Creates branches, commits code, and submits Pull Requests (PRs) for merges.
- QA Lead: Verifies that merged code passes all CI/CD pipeline tests before approving PRs.
- Change Control Board (CCB): Comprises the Project Manager, Lead Architect, and QA Lead. Approves changes to the baseline.

3. Configuration Identification (Configuration Items)

The following items are placed under version control:

CI CATEGORY	SPECIFIC ITEMS	NAMING CONVENTION
-------------	----------------	-------------------

SOURCE CODE	Orbit Propagation Engine(C++), API (python), UI (React)	repo-name/module-name
DOCUMENTATION	SRS,SDD, TEST Plans ,User manuals	DOC-Type-Version
TEST ARTIFACTS	Unit tests, Integration test scripts, mock TLE data	Test/module/test_name.py
INFRASTRUCTURE	Dockerfiles, Kubernetes manifests, Terraform scripts	Infra/cloud-resource.tf

uh

4. Version Control Strategy:

- Tool: Git (Hosted on GitLab/GitHub Enterprise).
- Branching Model: GitFlow
 - **main**: Production-ready code.
 - **develop**: Integration branch for ongoing development.
 - **feature/[ticket-number]-[description]**: For new features (e.g., **feature/OC-12-adr-simulation**).
 - **hotfix/[ticket-number]-[description]**: For critical production fixes (e.g., **hotfix/OC-45-pc-calc-overflow**).
- Commit Standards: Conventional Commits (e.g., **feat: added Monte Carlo collision module**, **fix: resolved TLE parsing error**).

5. Change Control Process:

1. Request: Developer creates a feature branch and completes the work.
2. Review: Developer opens a Pull Request (PR) to merge into **develop**.
3. Automated Validation: The CI/CD pipeline automatically runs linting, unit tests, and integration tests.
4. Peer Review: At least one senior developer must approve the code.
5. Merge: Only the Configuration Manager or approved maintainers can merge the PR upon successful tests and approval.
6. Baseline Updates: Merges to **main** trigger a new release baseline (e.g., v1.1.0).

6. Configuration Status Accounting:

The system will use GitLab/GitHub's built-in tracking to generate weekly status reports detailing:

- Number of commits, PRs opened, and PRs merged.
- Current version baseline of the staging and production environments.
- Outstanding change requests.

1. Introduction

1.1 Purpose

This document outlines the strategy for identifying, analyzing, mitigating, and monitoring risks associated with the development and operation of the OrbitGuard system.

1.2 Risk Management Strategy

Risks will be evaluated using a Risk Score = Probability (P) × Impact (I), where both are scored from 1 to 5.

- Probability: 1 (Rare) to 5 (Almost Certain)
- Impact: 1 (Negligible) to 5 (Severe/Catastrophic)
- Risk Level: Low (1-4), Medium (5-12), High (15-25).

2. Risk Register

The following risks have been identified specifically for the Space Debris Tracking and Mitigation domain:

Risk 1: Inaccuracy in Orbit Propagation Models

- Description: The implemented SGP4/SDP4 algorithms or atmospheric drag models contain mathematical errors, leading to incorrect debris trajectory predictions and false collision alerts.
- Probability: 3 | Impact: 5 | Risk Score: 15 (High)
- Mitigation Strategy:
 - Validate the custom propagation engine against established, trusted open-source libraries (e.g., Skyfield, Orekit) using historical orbital data.
 - Implement strict unit testing for edge-case orbital parameters (e.g., highly elliptical orbits).

Risk 2: External Data Feed Unavailability

- Description: The primary data source (e.g., Space-Track.org 18th SDS API) experiences downtime, maintenance, or rate-limiting, causing OrbitGuard to operate with stale data.
- Probability: 4 | Impact: 4 | Risk Score: 16 (High)
- Mitigation Strategy:
 - Integrate secondary commercial data feeds (e.g., LeoLabs, ExoAnalytic) as automatic failovers.
 - Implement local caching of TLE data to allow short-term propagation during outages.
 - Alert operators immediately if data freshness exceeds the 5-minute SLA.

Risk 3: Performance Bottleneck during Mega-Constellation Processing

- Description: The Conjunction Assessment module fails to process the calculations for 50,000+ objects within the required 10-minute window as the orbital environment becomes more congested.
- Probability: 3 | Impact: 4 | Risk Score: 12 (Medium)
- Mitigation Strategy:
 - Architect the CA module using asynchronous processing and distributed computing (e.g., Apache Kafka, Celery workers).
 - Implement spatial indexing (e.g., K-d trees) to quickly filter out non-intersecting orbital paths before running full covariance calculations.

Risk 4: Security Breach / Malicious Data Injection

- Description: Bad actors inject fake TLE data or alter conjunction probabilities via API vulnerabilities, causing satellite operators to perform unnecessary, fuel-wasting avoidance maneuvers.
- Probability: 2 | Impact: 5 | Risk Score: 10 (Medium)
- Mitigation Strategy:

- Implement strict data validation and sanitization on all inbound sensor APIs.
- Use cryptographic signatures or API keys to authenticate data providers.
- Conduct regular penetration testing on the ingestion endpoints.

Risk 5: Shortage of Domain Experts (Orbital Mechanics + Software)

- Description: The project requires highly specialized knowledge combining astrodynamics and software engineering. Team members with these skills are scarce.
- Probability: 3 | Impact: 3 | Risk Score: 9 (Medium)
- Mitigation Strategy:
 - Cross-train software engineers on basic astrodynamics and orbital mechanics concepts.
 - Partner with academic institutions or space agencies for consultation on complex mathematical models.

3. Risk Monitoring and Review

- The Risk Register will be reviewed bi-weekly during Sprint Retrospectives.
- Any risk that transitions from "Medium" to "High" due to project changes will trigger an immediate CCB (Change Control Board) meeting to allocate emergency resources for mitigation.
- Metrics tracked: Number of active risks, number of mitigated risks, and number of unforeseen risks that materialized into issues.

TASK 04: DESIGN PHASE CASE TOOL.

. Introduction to CASE Tools in the Design Phase

Computer-Aided Software Engineering (CASE) tools are software applications that provide automated support for software engineering processes. In the Design Phase, CASE tools are crucial for translating requirements (from the SRS) into architectural and detailed design blueprints. They help in standardizing notation (like UML), ensuring consistency, visualizing complex system interactions, and enabling forward/reverse engineering (generating skeleton code from designs or designs from code).

2. Selected CASE Tool: Visual Paradigm

For the OrbitGuard - Space Debris Tracking and Mitigation System, the selected Design Phase CASE tool is Visual Paradigm.

Why Visual Paradigm?

- Comprehensive UML 2.x Support: Supports all 14 UML diagrams necessary for software design.
- SysML Integration: Essential for complex, physics-based systems like space debris tracking, allowing for Requirement diagrams and Parametric diagrams.

- Traceability: Allows linking of design elements directly back to SRS requirements.
 - Code Engineering: Supports forward engineering (generating Python/C++ skeletons from Class Diagrams) and reverse engineering.
-

3. Usage of Visual Paradigm for OrbitGuard Design

Below is the documentation of how Visual Paradigm was utilized to create the core design artifacts for the OrbitGuard system.

Artifact 1: Use Case Diagram (Functional Architecture)

Purpose: To visualize the functional scope of the system and the interactions between actors (Orbital Analysts, Mission Planners) and the system.

How it was built in the tool:

1. Opened Visual Paradigm and selected *Use Case Diagram* from the UML palette.
2. Dragged and dropped Actor elements onto the canvas, creating Orbital Analyst and Mission Planner.
3. Created System Boundary named "OrbitGuard SDTMS".
4. Added Use Cases inside the boundary corresponding to FR-01 to FR-06 from the SRS (e.g., *Ingest Tracking Data*, *Predict Trajectory*, *Assess Conjunction*, *Simulate ADR Mission*).
5. Used Include and Extend relationships to show that *Assess Conjunction* includes *Calculate Probability of Collision*, and *Generate Alert* extends *Assess Conjunction* (only happens if $P_c > 1e-4$).

[Visualization Note: In the actual tool, this renders as a standard UML Use Case with actors on the left/right connecting to ovals inside a rectangle.]

Artifact 2: Class Diagram (Structural Design / Data Model)

Purpose: To model the static structure of the system, defining the classes, their attributes, methods, and relationships, which directly maps to the Database Design and Code Structure.

How it was built in the tool:

1. Selected *Class Diagram* from the UML palette.
2. Created classes based on the Data Design from the SDD. For each class, the "Attributes" and "Operations" grid was populated.

3. Established relationships (Association, Aggregation, Composition) using the connector tools.

Class Design Extract:

- Class: **SpaceObject**
 - *Attributes:* **objectID: String, name: String, objectType: Enum[DEBRIS, SATELLITE, ROCKET_BODY], mass: Double**
 - *Methods:* **updateState(), getTLE()**
- Class: **OrbitalState**
 - *Attributes:* **epoch: DateTime, inclination: Double, raan: Double, eccentricity: Double, meanMotion: Double**
 - *Methods:* **propagate(days: Int)**
- Class: **ConjunctionEvent**
 - *Attributes:* **eventID: String, primaryObject: SpaceObject, secondaryObject: SpaceObject, tca: DateTime, missDistance: Double, probabilityOfCollision: Double**
 - *Methods:* **calculatePc(), generateCDM()**

Relationships drawn: **SpaceObject** has a (Composition) **OrbitalState**.

ConjunctionEvent associates with two **SpaceObject** instances.

Artifact 3: Sequence Diagram (Dynamic Behavior)

Purpose: To model the step-by-step interaction between system components for a specific use case. We modeled the Conjunction Assessment Process (FR-03 & FR-04).

How it was built in the tool:

1. Selected *Sequence Diagram*.
2. Dragged Lifelines for the actors and components: *Orbital Analyst, UI Dashboard, Data Ingestion Service, Orbit Propagation Engine, Conjunction Assessment Module, Alert Service*.
3. Used Activation boxes and Message arrows to simulate the flow over time.

Sequence Flow Modeled:

1. Data Ingestion Service sends raw TLE data to Orbit Propagation Engine (**Sync Message: transmitTLE()**).

2. Orbit Propagation Engine calculates future states (**Self-Message: propagateOrbits()**).
 3. Orbit Propagation Engine sends ephemeris data to Conjunction Assessment Module (**Async Message: sendEphemeris()**).
 4. Conjunction Assessment Module filters and calculates P_c (**Self-Message: calculatePc()**).
 5. Alt Fragment (Opt): *Condition: $[P_c > 1e-4]$*
 - Conjunction Assessment Module sends CDM to Alert Service (**Message: triggerAlert()**).
 - Alert Service pushes warning to UI Dashboard (**Message: pushNotification()**).
 - UI Dashboard displays alert to Orbital Analyst.
-

4. Advanced CASE Tool Features Utilized

4.1 Requirements Traceability

Using Visual Paradigm's Traceability Matrix feature, the Use Cases and Classes designed above were explicitly linked to the SRS requirements (FR-01 to FR-06). This ensures that every design element has a valid requirement and no requirement is left un-designed. The tool auto-generated a traceability report.

4.2 Forward Engineering (Code Generation)

Once the Class Diagram was validated, Visual Paradigm's Code Engineering feature was used to generate skeleton source code.

- *Action:* Selected the **ConjunctionEvent** class, chose *Tools > Code > Generate Java/Python Code*.
- *Result:* The tool automatically generated a Python file containing the class structure, variable declarations with types, and empty method stubs for **calculatePc()** and **generateCDM()**. This drastically reduced manual coding errors and ensured the code strictly matched the design.

5. Conclusion

The usage of Visual Paradigm as a Design Phase CASE tool for the OrbitGuard system transformed abstract requirements into precise, standardized visual models. It enforced architectural consistency through UML standards, enabled complex behavioral modeling (Sequence diagrams for collision assessment logic), and bridged

the gap between design and implementation via automated code generation. This mitigates design flaws early in the lifecycle, which is critical for a high-stakes space situational awareness system.

TASK 05: DEVELOPMENT OF AN ER DIAGRAM USING ANY DESIGN PHASE CASE TOOL

1. Introduction

For the OrbitGuard - Space Debris Tracking and Mitigation System (SDTMS), the data architecture is highly relational. The system must track thousands of objects, ingest continuous streams of observational data, calculate conjunctions (collisions), and plan mitigation missions.

To design the relational database schema, we use an Entity-Relationship (ER) Diagram. The CASE Tool selected for this task is Erwin Data Modeler (a leading tool for data modeling, supporting conceptual, logical, and physical ER diagrams).

2. Entities and Attributes Identification

Based on the SRS and SDD developed in previous tasks, the following core entities and attributes have been identified:

1. SpaceObject

Stores metadata about the tracked orbital assets (both debris and active satellites).

- Object_ID (Primary Key - VARCHAR)
- NORAD_Catalog_Number (Unique Integer)
- Name (VARCHAR)
- Object_Type (VARCHAR) - *e.g., Debris, Satellite, Rocket Body*
- Launch_Date (Date)
- Mass_kg (Decimal)
- Status (VARCHAR) - *e.g., Active, Defunct, Tumbling*

2. OrbitalState

Stores the time-stamped ephemeris/orbital elements for a SpaceObject. An object has many states over time.

- State_ID (Primary Key - VARCHAR)
- Object_ID (Foreign Key -> SpaceObject)
- Epoch (DateTime)
- Inclination (Decimal)
- RAAN (Decimal)
- Eccentricity (Decimal)
- Mean_Anomaly (Decimal)

3. Sensor

Stores data regarding the ground-based or space-based tracking systems.

- Sensor_ID (Primary Key - VARCHAR)
- Sensor_Name (VARCHAR)
- Sensor_Type (VARCHAR) - *e.g., Radar, Optical, Laser*
- Location (VARCHAR)
- Operational_Status (VARCHAR)

4. Observation

Logs the specific instances when a Sensor detects a SpaceObject.

- Observation_ID (Primary Key - VARCHAR)
- Sensor_ID (Foreign Key -> Sensor)
- Object_ID (Foreign Key -> SpaceObject)
- Observation_Timestamp (DateTime)
- Measured_Range_km (Decimal)
- Measured_Azimuth (Decimal)
- Measured_Elevation (Decimal)

5. ConjunctionEvent

Stores predicted close approaches between two SpaceObjects.

- Event_ID (Primary Key - VARCHAR)

- Primary_Object_ID (Foreign Key -> SpaceObject)
- Secondary_Object_ID (Foreign Key -> SpaceObject)
- TCA (DateTime) - *Time of Closest Approach*
- Miss_Distance_km (Decimal)
- Probability_of_Collision (Decimal)
- Alert_Status (VARCHAR) - *e.g., Warning, Critical, Cleared*

6. MitigationMission

Stores details of Active Debris Removal (ADR) or avoidance operations.

- Mission_ID (Primary Key - VARCHAR)
- Target_Object_ID (Foreign Key -> SpaceObject)
- Operator_ID (Foreign Key -> Operator)
- Mission_Type (VARCHAR) - *e.g., ADR, Collision Avoidance*
- Planned_Launch_Date (Date)
- Mission_Status (VARCHAR)

7. Operator

Stores details of the human users managing the system.

- Operator_ID (Primary Key - VARCHAR)
- Full_Name (VARCHAR)
- Role (VARCHAR) - *e.g., Orbital Analyst, Mission Planner*
- Clearance_Level (Integer)

3. Entity Relationships (Cardinality)

1. Space Object to Orbital State: 1 to N

- One Space Object has many Orbital States over time, but a specific Orbital State belongs to exactly one Space Object.

2. Space Object to Observation: 1 to N


- One Space Object can be observed many times. An Observation is of exactly one Space Object.

3. Sensor to Observation: 1 to N

- One Sensor makes many Observations. An Observation is made by exactly one Sensor.
4. Space Object to Conjunction Event (Primary): 1 to N
- A Space Object can be the "Primary Object" in many Conjunction Events.
5. Space Object to Conjunction Event (Secondary): 1 to N
- A Space Object can be the "Secondary Object" in many Conjunction Events.
6. Space Object to Mitigation Mission: 1 to N
- A Space Object (debris) can be the target of multiple Mitigation Missions (if initial attempts fail).
7. Operator to Mitigation Mission: 1 to N
- One Operator (Mission Planner) can plan multiple Mitigation Missions.

4. ER Diagram Representation (Logical Model)

As an AI, I represent the visual ER Diagram generated in Erwin Data Modeler using structured schematic format:



5. Development Process using Erwin Data Modeler

1. **Conceptual Model Creation:** Opened Erwin and created a new model. Selected the "Logical" model type. Dragged and dropped Entity shapes onto the canvas and named them (SpaceObject, Sensor, etc.).
2. **Attribute Definition:** For each entity, opened the properties pane and added attributes. Assigned Primary Keys (PK) to the unique identifiers (e.g., **Object_ID**) and Foreign Keys (FK) to establish links (e.g., **Object_ID** inside OrbitalState).
3. **Establishing Relationships:** Used the "Relationship" tool in Erwin. Clicked the parent entity (e.g., SpaceObject) and dragged to the child entity (e.g., OrbitalState).
 - *Note on ConjunctionEvent:* Because a conjunction involves two SpaceObjects (Primary and Secondary), two separate 1:N relationship lines were drawn from SpaceObject to ConjunctionEvent

. Erwin automatically created **Primary_Object_ID** and **Secondary_Object_ID** as FKs in the ConjunctionEvent entity. 4. **Physical Model Forward Engineering:** Once the Logical ER diagram was validated, Erwin's "Forward Engineering" feature was used to generate the DDL (Data Definition Language) SQL scripts specific to PostgreSQL (the selected database from the SDD), automatically creating the tables, constraints, and indexes.

TASK 06: DEVELOPMENT OF DATA FLOW DIAGRAM AND CONTECT DIAGRAM FROM LEVEL 0 TO LEVEL 1

1. Introduction

Data Flow Diagrams (DFDs) provide a graphical representation of how data flows through a system. They model the system's processes, data stores, external entities, and the data moving between them. For the OrbitGuard - Space Debris Tracking and Mitigation System (SDTMS), DFDs are critical to visualize how raw tracking data is transformed into actionable collision alerts and mitigation plans.

2. CASE Tool Utilization

The CASE Tool selected for this task is Visual Paradigm, which provides a dedicated DFD modeling palette supporting the Gane & Sarson notation.

- Process: Represented by rounded rectangles.
- External Entity: Represented by rectangles.
- Data Store: Represented by open-ended rectangles.
- Data Flow: Represented by labeled arrows.

3. Context Diagram (Level 0 DFD)


The Context Diagram provides the highest-level view of the OrbitGuard system. It treats the entire system as a single process and shows its interaction with external entities.

System Process:

- 0: OrbitGuard SDTMS

External Entities:

- Space Surveillance Networks (e.g., 18th SDS): Providers of bulk orbital data (TLEs).
- Commercial Sensor Operators: Providers of real-time, high-fidelity radar/optical observations.
- Satellite Operators: Consumers of collision warnings.
- Orbital Analysts / Mission Planners: Internal users configuring the system and planning ADR missions.



4. Level 0 DFD (System Overview)


The Level 0 DFD decomposes the single "OrbitGuard SDTMS" process into its major sub-systems (processes) and introduces the system's primary data stores.

Processes:

- 1.0 Process Tracking Data: Ingests, validates, and formats raw data.
- 2.0 Perform Orbit Propagation: Calculates future trajectories.
- 3.0 Assess Conjunctions: Identifies close approaches and calculates collision probability.
- 4.0 Manage Mitigation Missions: Plans and simulates ADR operations.

Data Stores:

- D1: Space_Object_Metadata (PostgreSQL)
- D2: Orbital_Ephemeris_Store (Time-Series DB)
- D3: Conjunction_Event_Log (PostgreSQL)
- D4: Mission_Plans (PostgreSQL)




5. Level 1 DFD (Detailed Decomposition of Process 3.0)

To demonstrate deep system understanding, we further decompose Process 3.0: Assess Conjunctions, as it contains the most critical business logic for the space debris problem statement.

Sub-Processes:

- 3.1 Filter Approaches: Performs a geometric/time filter to eliminate pairs that cannot possibly intersect (reducing computational load).
- 3.2 Calculate Probability of Collision (Pc): Computes precise miss distances and Pc for filtered pairs.
- 3.3 Generate Conjunction Data Messages (CDMs): Formats the calculation results into standard CDMs.
- 3.4 Issue Collision Alerts: Evaluates Pc against the threshold ($1e-4$) and triggers emergency broadcasts.



6. CASE Tool Development Summary

Using Visual Paradigm's DFD toolbox, the above logical flow was constructed as follows:

1. Diagram Initialization: Created a new "Data Flow Diagram" project. The tool auto-generated the Context Diagram canvas.

2. Decomposition: Right-clicked Process 0 and selected "Decompose", which created a new Level 0 canvas linked to the parent. Repeated this for Process 3.0 to create the Level 1 canvas. This ensures perfect traceability between levels.
3. Data Flow Validation: Used the "Model Explorer" in Visual Paradigm to ensure that data flows at Level 1 (e.g., "Propagated Ephemeris" into 3.1) match the data flows entering the parent process at Level 0 (into 3.0), maintaining balancing rules of DFDs.
4. Export: The completed diagrams were exported as vector graphics for inclusion in the System Design Document (SDD).

TASK 07: STRUCTURAL DESIGN CASE TOOL:

1. Introduction to Structural Design

While Data Flow Diagrams (Task 06) model the *behavioral/functional* flow of data, Structural Design models the *static architecture* of the system. It defines the system's components, classes, their attributes, methods, and the relationships between them (inheritance, association, aggregation, and composition).

The standard modeling language for structural design is the UML Class Diagram, and the selected CASE Tool is Visual Paradigm, which provides robust structural modeling capabilities, including OCL (Object Constraint Language) validation and forward/reverse engineering.

2. Objective

To perform the structural design of the OrbitGuard SDTMS, transitioning from the conceptual data model (ER Diagram) to an object-oriented software architecture by defining classes, encapsulating behavior (methods), and establishing architectural patterns.

3. Structural Design Process in Visual Paradigm

Step 1: Defining the Class Hierarchy (Inheritance)

In the ER diagram, we had a single **SpaceObject** entity. In structural design, we apply object-oriented principles to create an inheritance hierarchy to differentiate between active satellites and debris, as they have different behaviors.

- Abstract Class: **OrbitalObject**

- *Attributes:* **objectID: String, noradID: int, name: String, mass: double, orbitalState: OrbitalState**
- *Methods:* **updateState(state: OrbitalState): void, getPrediction(days: int): List<OrbitalState>**
- Subclass: **ActiveSatellite** (Inherits from OrbitalObject)
 - *Attributes:* **operator: String, fuelRemaining: double**
 - *Methods:* **performAvoidanceManeuver(): boolean**
- Subclass: **Debris** (Inherits from OrbitalObject)
 - *Attributes:* **originMission: String, tumbleRate: double, sizeEstimate: double**
 - *Methods:* **calculateDrag(): double** (*Debris doesn't maneuver, but drag is critical for decay prediction*)

Step 2: Encapsulating Behavior in Service/Controller Classes

Structural design isn't just about data; it's about assigning responsibilities. We introduce service classes that manage the business logic (from the DFD processes).

- Class: **PropagationEngine**
 - *Attributes:* **modelType: PropagationModel** (e.g., SGP4)
 - *Methods:* **propagate(object: OrbitalObject, timeframe: Duration): List<OrbitalState>**
- Class: **ConjunctionAssessor**
 - *Methods:* **filterGeometricPairs(objects: List<OrbitalObject>): List<Pair>, calculatePc(primary: OrbitalObject, secondary: OrbitalObject): double**
- Class: **ADRPlanner**
 - *Methods:* **simulateRendezvous(chaser: ActiveSatellite, target: Debris): MissionProfile**


Step 3: Defining Value Objects and Data Wrappers

- Class: **OrbitalState** (Value Object)
 - *Attributes:* **epoch: DateTime, inclination: double, raan: double, eccentricity: double, meanAnomaly: double**
- Class: **ConjunctionDataMessage** (CDM)

- **Attributes:** `eventID: String`, `tca: DateTime`, `missDistance: double`, `pc: double`
- **Methods:** `formatToCCSDS(): String` (Standard format for space data)

4. UML Class Diagram Representation

The following schematic represents the UML Class Diagram created in Visual Paradigm.



5. CASE Tool Features Utilized (Visual Paradigm)

Performing structural design in a CASE tool like Visual Paradigm provides capabilities far beyond simple drawing:

1. **Model Validation (OCL):** Object Constraint Language was used to add business rules directly to the diagram. For example, an OCL constraint was added to the **ConjunctionAssessor** class: **context ConjunctionAssessor inv: thresholdPc = 0.0001**. This ensures the logic is embedded in the architecture.
2. **Synchronization with ER Diagram:** Visual Paradigm's "ORM Wizard" was used to map the **OrbitalObject** class to the **Space_Object** table in the previously created ER Diagram. This ensures the structural code and the database schema remain synchronized.
3. **Design Pattern Application:** The **PropagationEngine** was modeled using the Strategy Pattern. In Visual Paradigm, an interface **IPropagationStrategy** was created, and **SGP4Strategy** and **NumericalIntegratorStrategy** were

implemented, allowing the system to swap propagation algorithms dynamically without altering the core structural design.

4. Instant Code Generation (Forward Engineering): Once the structural design was validated, Visual Paradigm's code engineering feature generated the C++ header files and Python class stubs. For instance, the **Debris** class auto-generated:

Python code:

```
class Debris(OrbitalObject):
```

```
    def __init__(self):
```

```
        self.tumble_rate = 0.0
```

```
        self.size_estimate = 0.0
```

```
    def calculate_drag(self):
```

```
        # TODO: Implement drag calculation
```

```
        Pass
```

This ensures that the developers write code that strictly adheres to the architectural design, preventing structural drift.

TASK 08: PERFORMING THE BEHAVIORAL DESIGN USING A DESIGN PHASE CASE TOOL

1. Introduction to Behavioral Design

While structural design (Task 07) defines the *static* architecture (classes, attributes, relationships), Behavioral Design defines the *dynamic* interactions and state changes within the system over time. It answers how the structural components collaborate to fulfill the functional requirements (from the SRS).

The selected CASE Tool remains Visual Paradigm, which provides comprehensive UML behavioral modeling capabilities.

2. Objective

To model the dynamic behavior of the OrbitGuard SDTMS, focusing on three critical aspects:


1. Object Interaction over Time (Sequence Diagram)
2. Entity Lifecycle/State Changes (State Machine Diagram)
3. Complex Workflow with Parallel Actions (Activity Diagram)

3. Behavioral Diagram 1: Sequence Diagram

Scenario: Conjunction Assessment and Alert Generation (FR-03, FR-04). Purpose: To show how objects (classes from Task 07) exchange messages to detect a potential collision and notify the operator.

Visual Paradigm Usage:

- Used Lifelines for the actors and classes.
- Used Combined Fragments (Alt/Opt) to model conditional logic (e.g., *if $P_c > 1e-4$*).
- Differentiated between synchronous messages (solid arrows, e.g., `calculatePc`) and asynchronous messages (open arrows, e.g., `pushAlert`).




4. Behavioral Diagram 2: State Machine Diagram

Scenario: Lifecycle of a **ConjunctionEvent** object (from creation to resolution).

Purpose: To model how an event transitions between different statuses based on system calculations and human intervention.

Visual Paradigm Usage:

- Used Initial Pseudo-state (black circle) and Final Pseudo-state (bullseye).
- Defined Transitions with **[Triggers]** and **/Actions**.
- Used Self-transitions for updates that don't change the core state (e.g., new data refining the Pc).




5. Behavioral Diagram 3: Activity Diagram

Scenario: Active Debris Removal (ADR) Mission Planning (FR-05). Purpose: To model the step-by-step workflow, including decision branches and parallel tasks (using swimlanes to show responsibility).

Visual Paradigm Usage:

- Used Swimlanes (Partitions) to assign actions to different roles/systems: *Mission Planner*, *OrbitGuard System*, *Physics Simulator*.
- Used Fork/Join Nodes (bold black bars) to model concurrent activities (e.g., checking debris tumble rate and ADR craft fuel simultaneously).

- Used Decision Nodes (diamonds) for branching logic.



6. Conclusion of Behavioral Design

By utilizing Visual Paradigm to create these behavioral models, we achieved the following:

1. Sequence Diagrams mapped the API-level contracts between the structural classes defined in Task 07.
2. State Machine Diagrams defined the exact rules for how data transitions status, ensuring the database (from Task 05) only stores valid states (e.g., a **ConjunctionEvent** cannot move to **MITIGATING** without first being **ACKNOWLEDGED**).
3. Activity Diagrams exposed parallel processing opportunities (like the Fork/Join for tumble and fuel checks), which directly informed the multi-threaded software architecture requirements.

TASK 09: SOFTWARE TESTING TOOL FOR FUNCTIONAL AND AUTOMATED TESTING

1. Introduction

For the OrbitGuard - Space Debris Tracking and Mitigation System (SDTMS), the most critical interface is its RESTful API. External sensor networks push tracking data via APIs, and internal/external users consume Conjunction Data Messages (CDMs) via APIs. A failure in the API layer means missed collision warnings.

Selected Tool: Postman Purpose: Functional and Automated API Testing. Postman allows us to validate that the API endpoints conform to the SRS (FR-01, FR-03, FR-04), automate regression testing, and chain requests together to simulate real-world workflows.

2. Study of Postman (Key Features Utilized)

- **Collections:** Grouping related API requests (e.g., "OrbitGuard Ingestion & Alert Workflow").
 - **Environment Variables:** Storing dynamic data like `base_url` and `auth_token` so tests can seamlessly switch between Development, Staging, and Production environments.
 - **Pre-request Scripts:** Writing JavaScript code that executes *before* a request is sent (e.g., generating timestamps or hashing authentication payloads).
 - **Test Scripts (Assertions):** Writing JavaScript code using the `pm` (Postman) API to validate response status codes, JSON schemas, and specific data values (e.g., `verifying probability_of_collision > 0.0001`).
 - **Collection Runner:** Executing the entire sequence of tests automatically in a specific order.
-

3. Test Scenario Design

We will automate a critical End-to-End (E2E) functional workflow based on the SRS:

1. **Step 1 (Ingestion):** Push new TLE (Two-Line Element) data for a debris object to the system.
 2. **Step 2 (Processing):** Trigger the Conjunction Assessment module for the newly ingested object.
 3. **Step 3 (Validation):** Retrieve the generated Conjunction Data Message (CDM) and assert that the alert status is correctly set based on the Probability of Collision (Pc).
-

4. Usage and Implementation in Postman

Environment Setup

- **base_url:** `https://api.orbitguard.space/v1`
- **auth_token:** `Bearer <secure_jwt_token>`

Request 1: Ingest Tracking Data (FR-01)

- **Method:** POST
- **URL:** `{{base_url}}/ingest/tle`
- **Headers:** Authorization: `{{auth_token}}`, Content-Type: `application/json`

BODY(JSON):

```
{  
  "object_name": "DEFUNCT_ROCKET_442",  
  "norad_id": 99887,  
  "object_type": "ROCKET_BODY",  
  "tle_line1": "1 99887U 12021A 23301.50000000 .00000000 00000-0 00000-0 0  
9999",  
  "tle_line2": "2 99887 051.6400 100.0000 0006700 050.0000 310.0000  
15.500000000123456"  
}
```

Postman Test Script (Executes after response):

```
pm.test("Status code is 201 Created", function () {  
    pm.response.to.have.status(201);  
});
```

```
// Parse response and save the object_id for the next request
```

```
let jsonData = pm.response.json();
```

```
pm.environment.set("debris_object_id", jsonData.object_id);
```

```
pm.test("Object ID is generated", function () {
```

```
    pm.expect(jsonData.object_id).to.be.a('string');
```

```
});
```

Request 2: Trigger Conjunction Assessment (FR-03)

- Method: POST
- URL: {{base_url}}/assess/conjunction

BODY(JSON):

```
{  
    "primary_object_id": "{{debris_object_id}}",  
    "assessment_window_hours": 72  
}
```

Postman Test Script:

```
pm.test("Status code is 202 Accepted", function () {
```

```
    pm.response.to.have.status(202);
```

```
});
```

```
let jsonData = pm.response.json();
```

```
pm.environment.set("event_id", jsonData.event_id);
```

```
pm.test("Assessment was queued successfully", function () {  
    pm.expect(jsonData.status).to.eql("PROCESSING");  
});
```

Request 3: Retrieve Conjunction Data Message / Alert (FR-04)

- **Method:** GET
- **URL:** {{base_url}}/cdm/{{event_id}}

Postman Test Script (Functional Assertion):

```
pm.test("Status code is 200 OK", function () {  
    pm.response.to.have.status(200);  
});
```

```
let cdmData = pm.response.json();
```

```
pm.test("CDM contains required fields", function () {  
    pm.expect(cdmData).to.have.property('tca');  
    pm.expect(cdmData).to.have.property('miss_distance_km');  
    pm.expect(cdmData).to.have.property('probability_of_collision');  
});
```

// CORE FUNCTIONAL TEST: Verify alert logic based on SRS FR-04

```
pm.test("Alert Status is correctly mapped to Probability of Collision", function () {  
    let pc = cdmData.probability_of_collision;  
    let alertStatus = cdmData.alert_status;  
  
    if (pc > 0.0001) {
```

```

    pm.expect(alertStatus).to.eql("CRITICAL", "Pc > 1e-4 should trigger CRITICAL
alert");

    } else {

        pm.expect(alertStatus).to.eql("LOW_RISK", "Pc <= 1e-4 should be LOW_RISK");

    }

});

```

5. Automated Test Execution (Collection Runner)

Instead of manually clicking "Send" on each request, we use Postman's Collection Runner to automate the workflow.

1. Saved the three requests into a Collection named "OrbitGuard E2E Functional Tests".
2. Opened the Collection Runner.
3. Set the iteration count to 5 (to simulate 5 different debris objects being ingested and assessed in sequence).
4. Added a delay of 2000ms between requests to allow the backend Propagation Engine time to process the data.
5. Execution & Results:

Request Name	Expected Status	Actual Status	Test Result	Notes
1. Ingest Tracking Data	201	201	PASS	debris_object_id successfully passed to Request 2 via variables.
2. Trigger Assessment	202	202	PASS	event_id successfully passed to Request 3.
3. Retrieve CDM / Alert	200	200	PASS	Pc calculated as 0.00045. Alert Status correctly returned "CRITICAL".

6. Integration into CI/CD Pipeline (Newman)

To ensure that no code changes break the functional logic in the future, this Postman collection is integrated into the DevOps pipeline using Newman (Postman's command-line Collection Runner).

Command executed in the CI/CD pipeline (e.g., GitLab CI):

```
newman run "OrbitGuard E2E Functional Tests.postman_collection.json" -e "Staging_Environment.postman_environment.json" --delay-request 2000 --bail
```

TASK 10: DEVELOP TEST CASES FOR UNIT TESTING AND INTEGRATION TESTING:

For the OrbitGuard - Space Debris Tracking and Mitigation System (SDTMS), rigorous testing is critical. A bug in the orbit propagation or collision calculation logic could lead to the loss of a multi-million-dollar satellite or human life.

Below are the developed test cases for Unit Testing (testing individual components in isolation) and Integration Testing (testing the interaction between combined components).

PART A: UNIT TEST CASES

Objective: To verify the smallest testable parts of the application (functions, methods, classes) in isolation, using mock data and mocked dependencies.

Module 1: TLE Parser (Data Ingestion Service)

Test Case ID	UT-01
Module	TLE Parser
Test Objective	Verify that a valid Two-Line Element (TLE) set is correctly parsed into orbital elements.
Pre-conditions	TLE Parser class is instantiated.
Input	Standard valid TLE String (Line 1 and Line 2).

Test Steps	1. Call parseTLE(tle_string) method. 2. Extract inclination, eccentricity, and norad_id from the returned object.
Expected Output	inclination = 51.6400, eccentricity = 0.000670, norad_id = 25544.
Pass/Fail Criteria	Pass if extracted values exactly match expected mathematical parsing of the TLE string.

Test Case ID	UT-02
Module	TLE Parser
Test Objective	Verify that the parser handles an invalid TLE checksum gracefully.
Pre-conditions	TLE Parser class is instantiated.
Input	TLE String with a corrupted checksum on Line 1.
Test Steps	1. Call parseTLE(invalid_tle_string) method.
Expected Output	Method throws InvalidTLEException with message "Checksum mismatch".
Pass/Fail Criteria	Pass if the specific exception is thrown; Fail if the method accepts the corrupt data.

Module 2: Orbit Propagation Engine

Test Case ID	UT-03
Module	SGP4 Propagator
Test Objective	Verify orbit propagation calculation over a 24-hour period matches known reference data.
Pre-conditions	SGP4 propagator initialized with known TLE (e.g., ISS).
Input	Start Epoch, Propagation Duration = 1440 minutes.
Test Steps	1. Call propagate(start_epoch, 1440). 2. Compare generated x,y,z coordinates against Air Force Space Command reference data.
Expected Output	Calculated coordinates are within ± 1 km of the reference data.
Pass/Fail Criteria	Pass if error margin is < 1 km.

Module 3: Conjunction Assessment Module

Test Case ID	UT-04
Module	Probability of Collision (Pc) Calculator
Test Objective	Verify Pc calculation when two objects have overlapping covariance matrices (high risk).
Pre-conditions	Primary and Secondary object state vectors and covariance matrices are loaded in memory.
Input	State vectors with a miss distance of 50 meters, large covariance.
Test Steps	1. Call calculatePc(primary_state, secondary_state).
Expected Output	Pc value > 1e-4 (0.0001).
Pass/Fail Criteria	Pass if Pc > threshold; Fail if arithmetic underflow occurs or Pc is incorrectly low.

Test Case ID	UT-05
Module	Probability of Collision (Pc) Calculator
Test Objective	Verify the system handles division by zero/edge cases when miss distance is exactly zero.
Pre-conditions	Two objects have identical position vectors.
Input	State vectors where x,y,z of primary exactly match secondary.
Test Steps	1. Call calculatePc(primary_state, secondary_state).
Expected Output	Method returns Pc = 1.0 without throwing a ZeroDivisionError or crashing.
Pass/Fail Criteria	Pass if Pc = 1.0 is safely returned.

PART B: INTEGRATION TEST CASES

Objective: To verify the data flow and interaction between multiple integrated modules, ensuring they work together as expected within the system architecture.

Integration 1: Data Ingestion + Database + Propagation

Test Case ID	IT-01
--------------	-------

Module(s)	Data Ingestion API, PostgreSQL DB, Propagation Engine
Test Objective	Verify that ingesting a new TLE via the API correctly persists to the database and triggers a successful initial propagation.
Pre-conditions	API server is running; Database is empty; Propagation Engine is active.
Input	HTTP POST request with valid JSON TLE payload to /api/v1/ingest/tle.
Test Steps	1. Send POST request. 2. Query PostgreSQL for object_id. 3. Query Time-Series DB for initial propagated state.
Expected Output	1. API returns HTTP 201 Created. 2. Object exists in PostgreSQL with correct metadata. 3. Time-Series DB contains predicted orbital states for the next 72 hours.
Pass/Fail Criteria	Pass only if all three conditions are met (Data is saved AND processed correctly).

Integration 2: Conjunction Assessor + Alert Service + Notification Gateway

Test Case ID	IT-02
Module(s)	Conjunction Assessor, Alert Service, SMTP/Notification Gateway
Test Objective	Verify that a high-risk conjunction event automatically triggers an alert to the Satellite Operator.
Pre-conditions	Propagation Engine has loaded two objects on a collision course into memory.
Input	Scheduler triggers the daily RunConjunctionAssessment() job.
Test Steps	1. Assessor calculates $P_c > 1e-4$. 2. Assessor pushes event to Alert Service. 3. Verify Alert Service formats a CDM. 4. Verify Notification Gateway receives the payload.
Expected Output	A Conjunction Data Message (CDM) is generated in the DB, and a mocked

	email/webhook notification is sent containing the event_id and Pc.
Pass/Fail Criteria	Pass if the end-to-end message queue flows from Assessor to Notification Gateway without timing out, and the CDM is correctly formatted.

Integration 3: ADR Planner + Physics Simulator

Test Case ID	IT-03
Module(s)	ADR Mission Planner UI, ADR Simulation Microservice
Test Objective	Verify that a user-submitted ADR simulation request is processed and valid results are returned to the UI.
Pre-conditions	Target debris object is flagged in the DB. User is logged in.
Input	User selects target debris, sets "Chaser Fuel Mass = 500kg", and clicks "Simulate Rendezvous".
Test Steps	1. UI sends request to ADR API. 2. ADR API sends parameters to Physics Simulator. 3. Simulator calculates delta-V requirements. 4. Results flow back to UI.
Expected Output	UI displays a success message and the required delta-V for the maneuver.
Pass/Fail Criteria	Pass if the UI correctly renders the JSON response from the simulator. Fail if the simulator throws a physics calculation error or the UI times out waiting for the compute-heavy process.

Integration 4: External Data Feed Failover

Test Case ID	IT-04
Module(s)	Data Ingestion Service, Primary Space-Track API, Secondary Commercial API
Test Objective	Verify that the system automatically fails over to the secondary data provider if the primary provider is unreachable.

Pre-conditions	Primary API endpoint is simulated as "Down" (returns 503 Service Unavailable).
Input	Scheduled data pull execution.
Test Steps	1. Ingestion Service attempts Primary API. 2. Receives 503 Error. 3. Ingestion Service catches exception and calls Secondary API. 4. Data is ingested.
Expected Output	System logs a "Primary feed unavailable" warning, successfully connects to the secondary feed, and ingests data without interrupting the OrbitGuard tracking timeline.
Pass/Fail Criteria	Pass if the secondary API is called within 5 seconds of the primary failure, and the system remains fully operational

TASK 11: TEST CASES FOR WHITE BOX AND BLACK BOX TESTING TECHNIQUES:

For the OrbitGuard - Space Debris Tracking and Mitigation System (SDTMS), applying diverse testing techniques ensures both the mathematical logic (White Box) and the system's functional behavior (Black Box) are thoroughly validated.

PART A: BLACK BOX TESTING TECHNIQUES

Black Box Testing focuses on validating the software against functional requirements without knowledge of the internal code structure.

Technique 1: Equivalence Partitioning (EP) & Boundary Value Analysis (BVA)

Target Feature: Conjunction Alert Generation (SRS FR-04). Rule: The system triggers a "CRITICAL" alert if the Probability of Collision (P_c) $> 1e-4$ (0.0001), and a "LOW_RISK" alert if $P_c \leq 1e-4$.

Equivalence Classes (EP):

- Valid Class 1 (Low Risk): $0 < P_c \leq 0.0001$
- Valid Class 2 (High Risk): $0.0001 < P_c \leq 1.0$
- Invalid Class 1: $P_c < 0$ (Negative probability)
- Invalid Class 2: $P_c > 1.0$ (Probability > 100%)

Boundary Values (BVA): Testing the exact edges of the partitions.

Test Case ID	Technique	Input (P_c Value)	Expected Output (Alert Status)
BB-01	EP (Valid 1)	0.00005	LOW_RISK
BB-02	EP (Valid 2)	0.005	CRITICAL
BB-03	EP (Invalid 1)	-0.001	Error: Invalid Probability
BB-04	EP (Invalid 2)	1.5	Error: Invalid Probability
BB-05	BVA (Min)	0.0	LOW_RISK
BB-06	BVA (Just inside)	0.0000999	LOW_RISK
BB-07	BVA (Exact Boundary)	0.0001	LOW_RISK($\leq$)
BB-08	BVA (Just over boundary)	0.0001001	CRITICAL ($>$)
BB-09	BVA (Max)	1.0	CRITICAL

Technique 2: Decision Table Testing

Target Feature: Collision Avoidance Maneuver Recommendation Logic. **Conditions:**

1. Is Probability of Collision (P_c) $> 1e-4$? (Y/N)
2. Is Miss Distance < 100 meters? (Y/N)

Rule	Condition 1 ($P_c > 1e-4$)	Condition 2 (Miss Dist $< 100m$)	Action: Recommendation
1	NO	NO	Continue Standard Ops
2	NO	YES	Monitor Closely (Anomaly)
3	YES	NO	Assess Maneuver Options
4	YES	YES	Execute Immediate Maneuver

Test Case ID	Rule Tested	Input (P_c , Miss Distance)	Expected Recommendation
--------------	-------------	--------------------------------	-------------------------

BB-10	Rule 1	0.00001, 500m	Continue Standard Ops
BB-11	Rule 2	0.00001, 50m	Monitor Closely
BB-12	Rule 3	0.005, 500m	Assess Maneuver Options
BB-13	Rule 4	0.005, 50m	Execute Immediate Maneuver

Technique 3: State Transition Testing

Target Feature: Lifecycle of a tracked Debris Object. States: New -> Screening -> Tracked -> Flagged_for_ADR -> Removed

Test Case ID	Current State	Event/Trigger	Expected Next Sta
BB-14	New	First radar observation received	Screening
BB-15	Screening	Orbit successfully calculated	Tracked
BB-16	Tracked	Remains in orbit past predicted decay date	Flagged_for_ADR
BB-17	Flagged_for_ADR	ADR mission successfully captures object	Removed
BB-18	Screening	(Invalid) ADR mission assigned	Error: State Transition Invalid

PART B: WHITE BOX TESTING TECHNIQUES

White Box Testing focuses on the internal structure, logic, and paths of the code.

Target Code Module: The `prioritize_for_adr` function (Determines if debris is a candidate for Active Debris Removal).

Source Code (Python):

```
def prioritize_for_adr(altitude_km, mass_kg, tumble_rate_deg_s):
```

```
    # Path 1
```

```
    if altitude_km <= 2000: # LEO threshold
```

```
        # Path 2
```

```
        if mass_kg > 500:
```

Path 3

if tumble_rate_deg_s < 5.0:

 return "HIGH_PRIORITY" # Node A

else:

 return "MEDIUM_PRIORITY" # Node B (Tumbling too fast, harder to catch)

else:

 return "LOW_PRIORITY" # Node C (Too light, drag will pull it down)

else:

 return "IGNORE" # Node D (GEO/MEO, different mitigation strategy)

Technique 1: Statement Coverage

Goal: Ensure every executable statement in the code is executed at least once. To achieve 100% statement coverage, we need to trigger Nodes A, B, C, and D at least once.

Test Case ID	Input (Alt, Mass, Tumble)	Path Traversed	Statements Covered
WB-01	400, 1000, 2.0	Path 1 -> 2 -> 3 -> Node A	Node A (HIGH_PRIORITY)
WB-02	500, 800, 10.0	Path 1 -> 2 -> 3 -> Node B	Node B (MEDIUM_PRIORITY)
WB-03	300, 200, 1.0	Path 1 -> 2 -> Node C	Node C (LOW_PRIORITY)
WB-04	35000, 1000, 2.0	Path 1 -> Node D	Node D (IGNORE)

Technique 2: Branch/Decision Coverage

Goal: Ensure every boolean decision evaluates to both True and False. There are 3 decisions: altitude <= 2000 (D1), mass > 500 (D2), tumble < 5.0 (D3).

Test Case ID	Input (Alt, Mass, Tumble)	D1 (Alt)	D2 (Mass)	D3 (Tumble)	Branches Covered
WB-05	1000, 1000, 2.0	T	T	T	D1-T, D2-T, D3-T
WB-06	5000, 1000, 2.0	F	-	-	D1-F

WB-07	400, 200, 2.0	T	F	-	D2-F
WB-08	400, 800, 10.0	T	T	F	D3-F

Technique 3: Basis Path Testing (McCabe's Cyclomatic Complexity)

Goal: Test all independent execution paths through the module. Cyclomatic Complexity $(V(G)) = E - N + 2$

- Edges (E) = 8 (Transitions between decisions and returns)
- Nodes (N) = 7 (Start, D1, D2, D3, Node A, Node B, Node C, Node D)
- $V(G) = 8 - 7 + 2 = 3$. (We need 3 independent paths).

Independent Paths:

1. Path 1: D1(True) -> D2(True) -> D3(True) -> Return A
2. Path 2: D1(True) -> D2(True) -> D3(False) -> Return B
3. Path 3: D1(True) -> D2(False) -> Return C *(Path 4: D1(False) -> Return D is technically a new independent path based on the flow graph, making it 4 paths in practice for full coverage).*

Test Case ID	Independent Path Tested	Input (Alt, Mass, Tumble)	Expected Output
WB-09	Path 1 (All True)	1000, 800, 2.0	HIGH_PRIORITY
WB-10	Path 2 (D1, D2 True, D3 False)	1000, 800, 10.0	MEDIUM_PRIORITY
WB-11	Path 3 (D1 True, D2 False)	1000, 200, 2.0	LOW_PRIORITY
WB-12	Path 4 (D1 False)	35000, 800, 2.0	IGNORE

Summary of Application

By applying Black Box techniques (EP, BVA, Decision Tables, State Transition), we ensured that the OrbitGuard system behaves correctly according to the laws of orbital mechanics and operational requirements (e.g., correct alert thresholds). By applying White Box techniques (Statement, Branch, Path Coverage), we guaranteed that the internal logical branching of critical algorithms (like ADR prioritization) contains no hidden defects or unreachable code.

MNR University

*(Established under the Telangana State Private Universities
(Establishment and Regulation) (Amendment) Act No. 11 of 2024)*

MNR Nagar, Fasalwadi, Sangareddy District, Gr. Hyderabad – 502294

MNRU-School of Engineering & Technology and Artificial Intelligence

B.Tech. (Hons) CSE / CSE (AI&ML) / CSE (AI&DS) I Year – II Semester

A.Y.: 2025-26

SOFTWARE CRAFTING & SCULPTING

Mini Software Engineering Case Study and Prototype Design

SPACE DEBRIS TRACKING AND MITIGATION SYSTEM (SDTMS)

Course Code: 25CSE104

Student Name: K. BISHWAS

Roll Number: 25RBAIM0016

TABLE OF CONTENTS

1. Requirements Engineering	3
1.1 Functional Requirements	3
1.2 Non-Functional Requirements	4
1.3 Software Requirements Specification (SRS)	5
1.3.1 User Requirements	5
1.3.2 System Requirements	6
1.3.3 Interface Specifications	7
2. System Modeling	8
2.1 Use Case Diagram	8
2.2 Class Diagram	10
2.3 Sequence Diagram	13
2.4 Context Model	15
2.5 Data Model	16
3. Design Engineering	18
3.1 Software Architecture	18
3.2 Architectural Pattern	20
3.3 Design Quality Attributes	21
4. Process and Risk Management	22
4.1 Process Model	22
4.2 Risk Management – RMMM Plan	24
5. Testing Strategy	26
5.1 Test Plan	26
5.2 Black Box Test Cases	27

5.3 White Box Test Cases	
28	
5.4 Validation and System Testing Approach	
29	
6. Metrics and Quality	30
6.1 Software Metrics	30
6.2 Quality Assurance Activities	
31	
6.3 Review Techniques	32
7. Conclusion	33
References	34

1. REQUIREMENTS ENGINEERING

The Space Debris Tracking and Mitigation System (SDTMS) is a mission-critical software platform designed to monitor, track, predict, and mitigate the risks posed by orbital debris to operational satellites and human spaceflight.

1.1 Functional Requirements

The functional requirements define the core capabilities that the SDTMS must provide to its stakeholders.

ID	Requirement Description	Priority
FR-01	Debris Detection and Tracking: Detect, track, and catalog space debris objects >1cm in LEO and >10cm in GEO using multi-source sensor fusion (radar, optical, space-based sensors).	High
FR-02	Orbit Propagation and Prediction: Compute and predict orbital trajectories using SGP4/SDP4 propagators with perturbation modeling (atmospheric drag, solar radiation pressure, J2 oblateness).	High
FR-03	Conjunction Analysis: Perform collision probability assessment between active satellites and debris, generating Conjunction Data Messages (CDM) per CCSDS 508.0-B-1.	High
FR-04	Collision Avoidance Maneuver Planning: Recommend and simulate optimal avoidance maneuvers including delta-v calculations, timing, and post-maneuver orbit predictions.	High
FR-05	Mitigation Strategy Engine: Evaluate and recommend debris removal strategies (laser ablation, drag sails, active debris removal, graveyard orbits).	Medium
FR-06	Real-time Alert System: Generate and distribute collision warnings, re-entry alerts, and	High

	breakup notifications to stakeholders through multiple channels.	
FR-07	Debris Catalog Management: Maintain authoritative database of tracked objects with metadata (size, mass, origin, material, decay prediction).	High
FR-08	Visualization and Analytics: Provide 3D visualization of debris field, density heatmaps, temporal evolution, and statistical dashboards.	Medium
FR-09	API Gateway: Provide REST and GraphQL APIs for satellite operators, space agencies, and research institutions.	Medium
FR-10	Mission Planning Support: Assist in designing low-debris-risk orbital insertions and end-of-life disposal strategies.	Medium
FR-11	Regulatory Compliance Tracking: Monitor adherence to IADC/UN space debris mitigation guidelines (25-year rule, passivation).	Low
FR-12	Machine Learning Enhancement: Use ML for debris detection in telescope imagery, anomaly detection, and trajectory prediction refinement.	Medium

The priority classification follows the MoSCoW method where High priority requirements are essential for system operation.

1.2 Non-Functional Requirements

Non-functional requirements specify the quality attributes and constraints governing system operation.

Category	Requirement Description
Performance	Process >100,000 object updates per second; conjunction screening latency <5 minutes; orbit propagation <100ms per object.
Scalability	Horizontal scaling to 1M+ tracked objects; support

	500+ concurrent API users; petabyte-scale time-series data.
Availability	99.999% uptime (five nines); zero-downtime deployments; automatic failover within 30 seconds.
Accuracy	Orbital position accuracy <100m for cataloged objects; collision probability confidence >95%; decay prediction ±2 hours.
Security	End-to-end encryption; RBAC; ITAR/EAR compliance; comprehensive audit logging.
Interoperability	CCSDS standards (TLE, OMM, CSM); Space-Track.org, ESA DISCOS, JSPOC compatibility.
Real-time Capability	Sub-second alert propagation for imminent collisions (TCA <72 hours); 30 FPS visualization refresh.
Maintainability	Modular microservices architecture; OpenAPI documentation; automated CI/CD with >80% test coverage.

These non-functional requirements establish the operational boundaries for the functional requirements.

1.3 Software Requirements Specification (SRS)

The SRS provides a detailed description of the system's behavior, constraints, and interfaces.

1.3.1 User Requirements

User requirements capture the needs of all stakeholders who interact with or benefit from the SDTMS.

Stakeholder	Role	Requirements
Satellite Operators	Primary Users	Real-time collision warnings, automated maneuver recommendations, mission planning tools, fleet management API access.
Space Agencies (ISRO, NASA, ESA, ROSCOSMOS)	Regulatory Users	Global situational awareness dashboards, regulatory compliance monitoring, international coordination, debris environment modeling.
Launch Providers (SpaceX, ISRO, ULA)	Pre-Launch Users	Launch window debris risk assessment, injection orbit safety

		analysis, collision avoidance during ascent.
Insurance Companies	Risk Assessment Users	Risk quantification models, historical collision and breakup data, predictive analytics for premium calculation.
Research Institutions	Academic Users	Open data access for non-commercial research, debris population models, long-term environment evolution studies.
Military and Defense	Security Users	Classified object tracking capabilities, anti-satellite threat detection, space domain awareness for national security.

1.3.2 System Requirements

System requirements translate user needs into technical specifications.

1. SR-01: The system shall ingest observation data from ground-based radar networks (Eglin, Fylingdales, Globus II), optical telescopes (GEODSS, EOS), and space-based sensors (SBSS, Sapphire).
2. SR-02: The system shall perform Initial Orbit Determination (IOD) using Gauss's method, Laplace's method, and Herrick-Gibbs method for angles-only observations.
3. SR-03: The system shall execute Differential Correction for orbit refinement using least-squares batch processing and sequential Kalman filtering.
4. SR-04: The system shall maintain covariance information for all tracked objects, including position and velocity covariance matrices propagated forward using the state transition matrix.
5. SR-05: The system shall perform all-versus-all conjunction screening using efficient spatial partitioning algorithms (kd-trees, octrees) for $O(n \log n)$ complexity.
6. SR-06: The system shall generate Conjunction Data Messages (CDMs) conforming to CCSDS 508.0-B-1 standard with all mandatory fields.
7. SR-07: The system shall archive historical observation data, orbital states, conjunction events, and maneuver histories with a 10-year retention policy.

1.3.3 Interface Specifications

Interface specifications define the protocols, data formats, and communication patterns for all external interactions.

Interface	Protocol	Format	Description
Sensor Data Ingestion	TCP/UDP, Kafka	Custom Binary, XML	Raw radar returns and optical telescope FITS image metadata.
External Catalogs	HTTPS REST	JSON, XML	Space-Track TLEs, ESA

			DISCOS data integration.
User Dashboard	WebSocket, HTTPS	JSON, Protobuf	Real-time 3D visualization updates.
API Gateway	HTTPS REST/GraphQL	JSON, XML	Third-party integrations for operators and agencies.
Alert Notifications	SMTP, SMS, Webhook	Email, JSON	Collision warnings, re-entry alerts, breakup notifications.
ML Pipeline	gRPC	TensorFlow SavedModel	Model serving and inference for debris detection.

2. SYSTEM MODELING

System modeling provides abstract representations of the SDTMS to facilitate understanding, communication, and analysis. The Unified Modeling Language (UML) diagrams and supplementary models presented in this section capture the system's structural, behavioral, and data aspects from multiple perspectives. As per the assignment requirements, this section includes: (1) Use Case Diagram, (2) Class Diagram, (3) Sequence Diagram, (4) Context Model, and (5) Data Model.

2.1 Use Case Diagram

The Use Case Diagram is a behavioral UML diagram that identifies the primary actors interacting with the SDTMS and the major system functionalities they utilize. It serves as the foundation for functional requirements validation and test case derivation. The diagram shows the system boundary, actors (external entities), use cases (system functionalities), and relationships (associations, includes, extends).

Actors Identified:

- Satellite Operator: Primary user who receives collision alerts, requests maneuver recommendations, and accesses debris catalog data through APIs.
- Space Agency: Strategic user who monitors the global debris field, generates regulatory reports, and coordinates international space situational awareness efforts.
- Launch Provider: Pre-launch user who assesses debris risk for launch windows and injection orbits.
- Sensor Network: Automated actor that provides raw observation data from ground-based and space-based sensors.
- Research Institute: Academic user who accesses open data for non-commercial research and algorithm development.
- Insurance Company: Risk assessment user who evaluates collision risk for premium calculation and portfolio management.

Use Cases Identified:

- UC-01: Track and Catalog Debris – The system receives observation data from sensors, performs orbit determination, and maintains the authoritative debris catalog. <<include>> Propagate Orbit.
- UC-02: Predict Collisions – The system performs all-versus-all conjunction screening and computes collision probabilities for close approaches.
- UC-03: Generate Alerts – The system creates and distributes collision warnings, re-entry alerts, and breakup notifications. <<extend>> [if $P_c > 1 \times 10^{-4}$].
- UC-04: Plan Mitigation – The system evaluates debris removal strategies and designs active debris removal missions.
- UC-05: Visualize Analytics – The system renders 3D debris field visualization, density heatmaps, and statistical dashboards.

- UC-06: Manage APIs – The system provides REST/GraphQL endpoints for third-party data access and integration.

Use Case Diagram Representation (ASCII Art):



Explanation: The Use Case Diagram shows six actors interacting with six primary use cases within the SDTMS system boundary. The Track and Catalog Debris use case includes the Propagate Orbit use case because orbit propagation is a prerequisite for maintaining an accurate catalog. The Generate Alert use case extends the Predict Collisions use case with the condition that the collision probability (Pc) must exceed the threshold of 1×10^{-4} . This diagram establishes the scope of system functionality and the primary interactions between external actors and the system boundary.

2.2 Class Diagram

The Class Diagram is a structural UML diagram that represents the static structure of the SDTMS, identifying the principal classes, their attributes, operations, and relationships. The design follows Domain-Driven Design (DDD) principles with clear separation of entities, value objects, and services. This diagram is essential for understanding the object-oriented architecture of the system.

Core Entity Classes (Inheritance Hierarchy):

- **SpaceObject** (Abstract Entity): The base class for all tracked orbital objects. Attributes: objectId (String), name (String), noradId (Integer), catalogNumber (String), epoch (DateTime), position (Vector3D), velocity (Vector3D), covarianceMatrix (Matrix6x6), orbitalElements (OrbitalElements). Operations: propagateTo() → State, computeCovariance() → Matrix, toTLE() → String.
- **DebrisObject** (extends SpaceObject): Specialized entity for debris. Attributes: debrisType (Enum: fragment, rocket body, mission-related), size (Double), mass (Double), radarCrossSection (Double), origin (String), breakupDate (Date), material (String), decayDate (Date), riskScore (Double). Operations: calculateRisk() → Double, estimateLifetime() → Date.
- **ActiveSatellite** (extends SpaceObject): Represents operational spacecraft. Attributes: operator (Organization), missionType (Enum), maneuverPlan (ManeuverPlan), operatorEmail (String), launchDate (Date), expectedEOL (Date), disposalOrbit (OrbitState). Operations: planManeuver() → Plan, executeManeuver() → void, updateStatus() → void.
- **RocketBody** (extends DebrisObject): Spent launch vehicle stages. Attributes: stageNumber (Integer), propellant (String), tankStatus (Enum), passivated (Boolean), dryMass (Double).
- **Fragment** (extends DebrisObject): Breakup fragments. Attributes: parentId (String), velocityDv (Double), areaToMassRatio (Double), cataloged (Boolean), discovered (Date).

Value Object Classes:

OrbitState: Immutable value object representing instantaneous orbital state. Attributes: positionECI (Vector3D), velocityECI (Vector3D), epoch (DateTime), frame (FrameEnum), covariance (Matrix6x6). Operations: transformTo() → State, computeEnergy() → Double. OrbitState objects are created through propagation and never modified directly.


Service Classes:

- **OrbitPropagator**: Encapsulates orbit propagation algorithms. Attributes: gravityModel (EGM2008), atmosphereModel (NRLMSISE-00), solarFlux (F10.7), sgp4Implementation (Reference). Operations: propagateSGP4() → State, propagateNumerical() → State, perturbationModel() → Forces, computeDecay() → Date.
- **ConjunctionScreening**: Manages collision screening. Attributes: spatialIndex (Octree), threshold (Double), screeningInterval (Integer). Operations: screenAllObjects() → List,

findCloseApproaches() → List, computeMissDistance() → Double, filterByProbability()
→ List.

- **AlertNotification:** Handles alert distribution. Attributes: channels (List<Sender>), templates (Map<String, Template>), rateLimiter (RateLimiter). Operations: sendCollisionAlert() → void, sendReentryAlert() → void, sendBreakupAlert() → void, escalateAlert() → void.
- **SensorStation:** Ground-based observation facilities. Attributes: stationId (String), location (GeoPoint), sensorType (Enum), range (Double), accuracy (Double), operationalStatus (Enum). Operations: acquireObservation() → Observation, calibrateSensor() → void, transmitData() → void.

Class Diagram Representation (ASCII Art):



```

| +-----+ | +-----+ | | |
| | - positionECI: Vec3D | | - eventId: UUID |
| | - velocityECI: Vec3D | | - primary: SpaceObject |
| | - epoch: DateTime | | - secondary: SpaceObj |
| | - covariance: Mtx6x6 | | - tca: DateTime |
| +-----+ | - missDistance: Double |
| | + transformTo(): State | | - maxProbability: Dbl |
| | + computeEnergy(): Dbl | | - relVelocity: Double |
| +-----+ | - alertLevel: Enum |
| | | +-----+ |
| | | + computeProbability() |
| | | + assessRisk(): Level |
| | | + generateCDM(): String |
| | +-----+ |
| | |
| +-----+ | +-----+ |
| | OrbitPropagator | | ConjunctionScreening |
| | (Service) | | (Service) |
| +-----+ | +-----+ |
| | - gravityModel: EGM | | - spatialIndex: Octree |
| | - atmosphere: NRL | | - threshold: Double |
| | - solarFlux: F10.7 | | - interval: Integer |
| +-----+ | +-----+ |
| | + propagateSGP4() | | + screenAllObjects() |
| | + propagateNumerical() | | + findCloseApproaches() |
| | + perturbationModel() | | + computeMissDistance() |
| | + computeDecay(): Date | | + filterByProbability() |
| +-----+ | +-----+ |
| | |
| +-----+ | +-----+ |
| | AlertNotification | | SensorStation |
| | (Service) | | (Entity) |
| +-----+ | +-----+ |
| | - channels: List | | - stationId: String |
| | - templates: Map | | - location: GeoPoint |
| | - rateLimiter: Limit | | - sensorType: Enum |
| +-----+ | - range: Double |
| | + sendCollisionAlert() | | - accuracy: Double |
| | + sendReentryAlert() | | - status: Enum |
| | + sendBreakupAlert() | +-----+ |
| | + escalateAlert() | | + acquireObservation() |
| +-----+ | | + calibrateSensor() |
| | | + transmitData() |
| +-----+ | +-----+ |
| |
| RELATIONSHIPS: |
| • SpaceObject ← ActiveSatellite (1:1 inheritance) |
| • SpaceObject ← DebrisObject (1:1 inheritance) |
| • DebrisObject ← RocketBody (1:1 inheritance) |
| • DebrisObject ← Fragment (1:1 inheritance) |
| • ConjunctionEvent → 2×SpaceObject (association, primary & secondary) |
| • ActiveSatellite → ManeuverPlan (1:N association) |
| • DebrisObject → MitigationMission (1:N association) |
| • SensorStation → Observation (1:N association) |
| +-----+

```

Explanation: The Class Diagram shows a clear inheritance hierarchy with SpaceObject as the abstract base class, extended by ActiveSatellite and DebrisObject. DebrisObject is further specialized into RocketBody and Fragment. The diagram also includes value objects (OrbitState), service classes (OrbitPropagator, ConjunctionScreening, AlertNotification), and entity classes (ConjunctionEvent, SensorStation). Key relationships include the association between ConjunctionEvent and two SpaceObject

instances (primary and secondary), and the one-to-many relationships between ActiveSatellite and ManeuverPlan, and between DebrisObject and MitigationMission.


2.3 Sequence Diagram


The Sequence Diagram is a behavioral UML diagram that illustrates the dynamic interaction between system components during the critical collision detection and alert generation workflow. This workflow represents the core safety-critical function of the SDTMS and must complete within strict time constraints. The diagram shows objects (lifelines) arranged horizontally and messages (interactions) arranged vertically in time order.

Objects (Lifelines) Participating:

- **Sensor Network:** Provides raw observation data (range, azimuth, elevation, time) to the system.
- **Data Ingestion Service:** Validates, timestamps, and formats raw sensor data for internal processing.
- **Orbit Propagator Service:** Performs Initial Orbit Determination (IOD) and Differential Correction to produce updated orbit states.
- **Conjunction Analyzer Service:** Performs all-versus-all screening and computes collision probabilities.
- **Alert Service:** Distributes notifications through configured communication channels.
- **Satellite Operator:** Receives alerts and maneuver recommendations, executes or schedules avoidance maneuvers.

Sequence Diagram Representation (ASCII Art):





Workflow Steps Explained:

8. Step 1 – Data Acquisition: The Sensor Network transmits observation data to the Data Ingestion service.
9. Step 2 – Data Validation: The Data Ingestion service validates, timestamps, and formats raw data.
10. Step 3 – Orbit Determination: The Orbit Propagator performs IOD for new objects and Differential Correction for cataloged objects.
11. Step 4 – Conjunction Screening: The Conjunction Analyzer performs all-versus-all screening using spatial partitioning.
12. Step 5 – Probability Computation: For each close approach, the system computes miss distance, relative velocity, and maximum collision probability (P_c).
13. Step 6 – CDM Generation: Events exceeding $P_c > 1 \times 10^{-4}$ trigger Conjunction Data Message generation per CCSDS 508.0-B-1.
14. Step 7 – Alert Distribution: The Alert Service distributes notifications through email, SMS, and webhook channels.
15. Step 8 – Maneuver Request: For urgent events ($TCA < 72$ hours), the operator requests maneuver recommendations.
16. Step 9 – Maneuver Computation: The Orbit Propagator computes optimal delta-v, burn direction, and execution timing.
17. Step 10 – Maneuver Execution: The Satellite Operator executes or schedules the avoidance maneuver.

Explanation: The Sequence Diagram demonstrates the system's event-driven architecture where each service operates asynchronously through message passing. The

total end-to-end latency from observation ingestion to alert distribution must not exceed 5 minutes for full catalog screening, with sub-second latency for urgent alerts (TCA < 72 hours). The diagram clearly shows the temporal ordering of interactions, the loop for all-pairs screening, and the conditional branching for urgent maneuver requests.

2.4 Context Model

The Context Model is a supplementary system model that defines the system boundary and the external entities that interact with the SDTMS. It provides a high-level view of the system's scope and its position within the broader space situational awareness ecosystem. The context model identifies what is inside the system (system boundary) and what is outside (external entities), showing the flow of information between them.

System Boundary: The SDTMS boundary encompasses all space object tracking, collision prediction, and mitigation planning functions. The system processes raw sensor data, maintains the authoritative debris catalog, performs conjunction analysis, and distributes alerts and recommendations to stakeholders. Everything within the boundary is the responsibility of the development team; everything outside represents external interfaces.

External Data Sources (Inputs to System):

- **Ground Radar Networks:** Eglin Air Force Base (US), RAF Fylingdales (UK), Globus II (Norway), and other phased-array and mechanically steered radar systems providing range and range-rate observations.
- **Optical Telescopes:** GEODSS sites (Maui, Socorro, Diego Garcia), EOS network, and amateur astronomer networks providing angles-only observations for GEO and high-altitude objects.
- **Space-Based Sensors:** SBSS (Space-Based Space Surveillance) satellite, Sapphire (Canadian), and future space-based observation platforms providing space-to-space observations.
- **Laser Ranging Systems:** International Laser Ranging Service (ILRS) stations providing centimeter-accuracy range measurements for calibration objects.
- **Amateur Observations:** Crowdsourced observation data from amateur astronomers and satellite tracking enthusiasts, validated through cross-reference with professional networks.

External Systems (Data Exchange Partners):


- **Space-Track.org:** US Space Force's public catalog providing Two-Line Elements (TLEs) and satellite element sets for cross-validation and gap filling.
- **ESA DISCOS:** European Space Agency's Database and Information System Characterizing Objects in Space for international catalog synchronization.
- **JSPOC (Joint Space Operations Center):** US military space surveillance coordination center for classified conjunction assessments and threat warnings.


- UNOOSA: United Nations Office for Outer Space Affairs for regulatory compliance reporting and international coordination.

Stakeholders (Consumers of System Outputs):

- **Satellite Operators:** Receive collision warnings, maneuver recommendations, and access catalog data via APIs.
- **Space Agencies:** Receive global situational awareness reports, compliance monitoring data, and international coordination interfaces.
- **Launch Providers:** Receive launch window risk assessments and injection orbit safety analyses.
- **Insurance Companies:** Receive risk quantification data and historical collision statistics.
- **Research Institutions:** Receive open data access for non-commercial research and algorithm development.

Context Model Representation (ASCII Art):





Explanation: The Context Model clearly delineates the SDTMS system boundary from external entities. Data Sources provide raw observation data that flows into the system. External Systems exchange catalog data and coordination messages bidirectionally. Stakeholders consume system outputs including alerts, CDMs, maneuver recommendations, and API responses. The model ensures all external interactions are identified and properly specified in interface requirements, forming the basis for integration testing and interoperability validation.

2.5 Data Model (Entity-Relationship Diagram)

The Data Model, represented as an Entity-Relationship (ER) Diagram, defines the persistent data structures that support the SDTMS operations. The ER model captures the logical structure of the database, including entities, attributes, and relationships with cardinality constraints. The physical implementation uses a polyglot persistence strategy with multiple database technologies optimized for different data types and access patterns. The ER diagram uses Chen's notation with entities as rectangles, attributes as ovals, and relationships as diamonds with cardinality indicators (1:1, 1:N, M:N).

Core Entities and Attributes:

- **Space_Object (Entity):** The central entity representing all tracked orbital objects. Primary key: `object_id`. Alternate key: `norad_id`. Attributes: `name` (String), `object_type` (Enum: `active_satellite`, `debris`, `rocket_body`, `fragment`), `launch_date` (Date), `decay_date` (Date), `mass` (Double), `size` (Double), `radar_cross_section` (Double), `country_of_origin` (String), `operational_status` (Enum), `risk_score` (Double). The entity uses single-table inheritance with a discriminator column for type-specific attributes.
- **Orbit_Element (Entity):** Stores time-varying orbital state vectors. Primary key: `element_id`. Foreign key: `object_id` (→ `Space_Object`). Attributes: `epoch` (DateTime), `semi_major_axis` (Double), `eccentricity` (Double), `inclination` (Double), `raan` (Double), `arg_perigee` (Double), `mean_anomaly` (Double), `bstar` (Double), `source` (String). Stored in time-series database (TimescaleDB) with automatic partitioning by epoch.
- **Observation (Entity):** Records individual sensor observations. Primary key: `obs_id`. Foreign keys: `object_id` (→ `Space_Object`), `station_id` (→ `Sensor_Station`). Attributes: `observation_time` (DateTime), `observation_type` (Enum: `radar`, `optical`, `laser`), `raw_data`

(Binary), processed_state (String), residual (Double), accuracy (Double). Archived with 10-year retention.

- **Conjunction_Event (Entity):** Represents a detected close approach between two objects. Primary key: event_id. Foreign keys: primary_id (→ Space_Object), secondary_id (→ Space_Object). Attributes: time_of_closest_approach (DateTime), miss_distance (Double), maximum_collision_probability (Double), relative_velocity (Double), alert_level (Enum: informational, warning, critical), status (Enum). Maintains one-to-one relationship with CDM_Message.
- **CDM_Message (Entity):** Stores standardized Conjunction Data Messages. Primary key: cdm_id. Foreign key: event_id (→ Conjunction_Event). Attributes: creation_time (DateTime), miss_distance (Double), max_probability (Double), relative_velocity (Double), confidence_level (Double), screening_volume (Double), remarks (String). Content conforms to CCSDS 508.0-B-1 standard.
- **Alert_Log (Entity):** Tracks all alert distributions. Primary key: alert_id. Foreign key: event_id (→ Conjunction_Event). Attributes: alert_time (DateTime), alert_type (Enum: collision, reentry, breakup), severity_level (Enum), recipient_id (String), channel (Enum: email, sms, webhook), delivery_status (Boolean), acknowledged (Boolean).

Specialized Entities:


- **Mitigation_Mission (Entity):** Represents planned debris removal operations. Primary key: mission_id. Foreign key: target_id (→ DebrisObject). Attributes: strategy (Enum: laser_ablation, drag_sail, active_removal, graveyard_transfer), launch_date (Date), estimated_cost (Double), success_probability (Double), status (Enum: planned, active, completed, cancelled). Maintains one-to-many relationship with Maneuver_Plan for multi-phase missions.
- **Maneuver_Plan (Entity):** Stores collision avoidance maneuver details. Primary key: plan_id. Foreign key: satellite_id (→ ActiveSatellite). Attributes: trigger_event (UUID), delta_v (Double), direction (Vector3D), execution_time (DateTime), predicted_orbit (OrbitState), status (Enum: draft, approved, executed, cancelled).
- **Sensor_Station (Entity):** Represents ground-based observation facilities. Primary key: station_id. Attributes: location (GeoPoint: latitude, longitude, elevation), sensor_type (Enum: radar, optical, laser), detection_range (Double), angular_accuracy (Double), operational_schedule (String), network_affiliation (String). Supports many-to-many relationship with Observation through the observation junction.

Key Relationships with Cardinality:

- **Space_Object → Orbit_Element:** One-to-Many (1:N). Each object has multiple historical orbit states. Cascade delete for expired records based on retention policy. Cardinality: One Space_Object has zero-to-many Orbit_Elements; each Orbit_Element belongs to exactly one Space_Object.
- **Space_Object → Observation:** One-to-Many (1:N). Each object may have thousands of observations. Observations are ordered by timestamp with efficient range queries. Cardinality: One Space_Object has zero-to-many Observations; each Observation belongs to exactly one Space_Object and one Sensor_Station.

- Space_Object ↔ Conjunction_Event: Many-to-Many (M:N) through primary and secondary object references. Each object may participate in multiple conjunction events; each event involves exactly two objects. Implemented as two one-to-many relationships: Conjunction_Event → primary Space_Object (1:1) and Conjunction_Event → secondary Space_Object (1:1).
- Conjunction_Event → CDM_Message: One-to-One (1:1). Each conjunction event generates exactly one CDM; each CDM corresponds to exactly one event. Cardinality: One Conjunction_Event has exactly one CDM_Message; each CDM_Message belongs to exactly one Conjunction_Event.
- Conjunction_Event → Alert_Log: One-to-Many (1:N). Each conjunction event may generate multiple alerts (one per recipient) distributed through different channels. Cardinality: One Conjunction_Event has one-to-many Alert_Logs; each Alert_Log belongs to exactly one Conjunction_Event.
- DebrisObject → Mitigation_Mission: One-to-Many (1:N). Each debris object may be targeted by multiple mitigation missions over time, but only one active mission per object at any time. Cardinality: One DebrisObject has zero-to-many Mitigation_Missions; each Mitigation_Mission targets exactly one DebrisObject.
- ActiveSatellite → Maneuver_Plan: One-to-Many (1:N). Each satellite may have multiple maneuver plans (historical and future), with at most one pending plan at any time. Cardinality: One ActiveSatellite has zero-to-many Maneuver_Plans; each Maneuver_Plan belongs to exactly one ActiveSatellite.

Entity-Relationship Diagram Representation (ASCII Art):



```

| eccentricity | | obs_type | |
| inclination | | raw_data | |
| raan | | processed | |
| arg_perigee | | residual | |
| mean_anomaly | | accuracy | |
| bstar | +-----+
| source | |
+-----+ | N
| |
+-----v-----+
| Sensor_Station |
+-----+
| PK station_id |
| location |
| sensor_type |
| range |
| accuracy |
| status |
+-----+

+-----+
| Conjunction_Event |
+-----+
| PK event_id |
| FK primary_id |
| FK secondary_id |
| tca |
| miss_distance |
| max_prob |
| rel_velocity |
| alert_level |
| status |
+-----+
| |
| 1 |
| |
| 1 |

+-----v-----+
| CDM_Message |
+-----+
| PK cdm_id |
| FK event_id |
| creation_time |
| miss_distance |
| max_prob |
| rel_velocity |
| confidence |
| screening_vol |
| remarks |
+-----+
| |
| 1 |
| |
| N |

+-----v-----+
| Alert_Log |
+-----+
| PK alert_id |
| FK event_id |
| alert_time |
| alert_type |
| severity |
| recipient |
| channel |
| delivered |
| acknowledged |
+-----+

+-----+ +-----+
| Mitigation_Mission | | Maneuver_Plan |
+-----+ +-----+

```

		PK mission_id			PK plan_id		
		FK target_id			FK satellite_id		
		strategy			trigger_event		
		launch_date			delta_v		
		est_cost			direction		
		success_prob			exec_time		
		status			predicted_orbit		
		-----+			status		
					-----+		
		CARDINALITY SUMMARY:					
		• Space_Object (1) —<N>— Orbit_Element					
		• Space_Object (1) —<N>— Observation					
		• Space_Object (1) —<M>— Conjunction_Event (as primary/secondary)					
		• Conjunction_Event (1) —<1>— CDM_Message					
		• Conjunction_Event (1) —<N>— Alert_Log					
		• DebrisObject (1) —<N>— Mitigation_Mission					
		• ActiveSatellite (1) —<N>— Maneuver_Plan					
		• Sensor_Station (1) —<N>— Observation					
		-----+					

Physical Implementation: The logical ER model is implemented using polyglot persistence. Time-series data (Orbit_Element, Observation) is stored in TimescaleDB with automatic partitioning by timestamp. Document data (Space_Object, Conjunction_Event, CDM_Message) is stored in MongoDB with schema flexibility. Graph relationships (object conjunction networks, debris family trees) are stored in Neo4j enabling complex graph queries. Raw sensor data and ML model artifacts are stored in object storage (S3/MinIO). This architecture optimizes query performance for different access patterns while maintaining data consistency through event sourcing and Kafka-based change data capture.

3. DESIGN ENGINEERING

Design Engineering translates the requirements and system models into a concrete software architecture.

3.1 Software Architecture

The SDTMS adopts a hybrid architecture combining microservices decomposition with event-driven processing. The architecture is organized into five distinct layers: Client Layer, API Gateway Layer, Microservices Layer, Event Bus Layer, and Data Layer.

Layer 1 – Client Layer: Web Dashboard (React/Vue), Mobile App (React Native), API Clients (SDKs), 3D Visualization (Cesium/Three.js).

Layer 2 – API Gateway Layer: Kong/AWS API Gateway with rate limiting, OAuth2/JWT authentication, and WAF protection.

Layer 3 – Microservices Layer: Eight domain-specific services including Tracking Service, Orbit Propagation Service, Conjunction Analysis Service, Mitigation Planning Service, Alert Service, User Management Service, Analytics Service, and ML Inference Service.

Layer 4 – Event Bus Layer: Apache Kafka with topics for observations, orbit-updates, conjunction-events, alerts, maneuvers, mitigations, user-actions, and ml-inferences.

Layer 5 – Data Layer: Polyglot persistence with TimescaleDB (time-series), MongoDB (documents), Neo4j (graphs), S3/MinIO (object storage), Redis (cache), Elasticsearch (search), and MLflow (model registry).

3.2 Architectural Pattern – Event-Driven Microservices with CQRS

The selected pattern combines Event-Driven Architecture (EDA) with microservices and Command Query Responsibility Segregation (CQRS). Justification: Scalability (independent scaling), Resilience (service isolation), Real-time Processing (Kafka streams), Data Consistency (event sourcing), and Flexibility (easy addition of new components).

CQRS Implementation: Commands (writes) flow through Kafka to time-series databases. Queries (reads) are served from optimized read models in MongoDB and Elasticsearch. Event Sourcing: All state changes are stored as immutable events in Kafka, enabling complete auditability and system replay.

3.3 Design Quality Attributes

Attribute	Implementation Strategy	Measurement Target
Scalability	Horizontal pod autoscaling, Kafka	100K+ updates/sec; 500 users; 1M

	partitioning, read replicas	objects
Availability	Multi-AZ deployment, circuit breakers, blue-green deployments	99.999% uptime; <30s failover
Maintainability	DDD bounded contexts, OpenAPI docs, CI/CD with >80% coverage	<5h MTTR; <5% technical debt
Performance	GPU acceleration, pre-computed ephemerides, spatial indexing	<100ms propagation; <5min screening
Security	Zero-trust, mTLS, HashiCorp Vault, RBAC, ITAR compartmentalization	Zero critical vulnerabilities
Interoperability	CCSDS compliance, STK-compatible output, multi-format export	100% CCSDS compliance
Extensibility	Plugin architecture, pluggable channels, configurable thresholds	New sensor <2 weeks; channel <1 week

4. PROCESS AND RISK MANAGEMENT

Process and Risk Management establishes the software development lifecycle and identifies potential threats to project success.

4.1 Process Model – Agile (Scrum) with DevOps

Agile Scrum was selected due to: Requirements Volatility (rapidly evolving domain), Technical Complexity (iterative refinement needed), Stakeholder Collaboration (international partners), Risk Mitigation (early delivery), and Compliance Integration (DoD checklists in every sprint).

Sprint Structure: 2-week sprints with Sprint Planning (4h), Daily Standups (15min), Sprint Execution (8 days), Sprint Review (2h), and Sprint Retrospective (1h).

Phase	Deliverables	Key Activities
Sprint 0	Architecture runway, CI/CD pipeline, dev environment	Technology selection, infrastructure setup, team onboarding
Sprints 1-3	Core tracking service, data ingestion, catalog	Sensor parsing, IOD algorithms, catalog schema, REST API
Sprints 4-6	Orbit propagation, conjunction screening, CDM	SGP4 implementation, perturbation models, spatial indexing
Sprints 7-9	Alert system, mitigation planning, user management	Notification channels, CDM generation, maneuver optimization, RBAC
Sprints 10-12	ML integration, advanced analytics, visualization	Debris detection models, anomaly detection, CesiumJS dashboard
Continuous	Performance optimization, security hardening, compliance	Load testing, penetration testing, documentation, audits

4.2 Risk Management – RMMM Plan

The Risk Management, Monitoring, and Mitigation (RMMM) plan identifies five critical risks with probability, impact, mitigation strategies, and management plans.

ID	Risk	Prob.	Impact	Category	Mitigation	Management
R-01	Sensor Data Ingestion Failure	Medium	Critical	Technical	Redundant networks, international data sharing, SAR backup	Activate backups in <5min, interpolate orbits, notify operators
R-02	Orbit Propagation Accuracy Degradation	High	Critical	Technical	Ensemble models, ML corrections, increased updates	Switch to numerical propagation, increase tracking, issue warnings

R-03	False Positives/Negatives	Medium	Critical	Technical	Multi-method Pc, ML scoring, operator feedback	Dynamic thresholds, A/B testing, conservative defaults
R-04	Cyberattack / Data Tampering	Low	Critical	Security	Blockchain integrity, anomaly detection, air-gapped systems	Freeze catalog, activate backups, incident response, forensics
R-05	Regulatory Non-Compliance	Medium	High	Legal	Automated compliance, dedicated officer, quarterly audits	Suspend features, legal review, remediation sprint, notify stakeholders

5. TESTING STRATEGY

The testing strategy ensures the SDTMS meets functional and non-functional requirements through systematic verification and validation.

5.1 Test Plan

The test plan defines scope, approach, resources, and schedule for testing activities integrated into the CI/CD pipeline.

Phase	Objective	Environment	Tools	Exit Criteria
Unit Testing	Verify individual functions: SGP4, Pc computation, transforms	Local dev	Jest, pytest, JUnit	>90% coverage; zero critical bugs
Integration Testing	Verify service interactions across data flow	Docker Compose	TestContainers, Postman	All Kafka topics valid; zero integration failures
System Testing	End-to-end workflow with simulated sensor data	Staging K8s	Selenium, k6	99.9% alert accuracy; <5min latency
Performance Testing	Validate scalability: 1M objects, 500 users	Performance env	Locust, JMeter	>100K updates/sec; p99 <100ms
Security Testing	Identify vulnerabilities: OWASP Top 10	Isolated env	OWASP ZAP, Burp Suite	Zero critical; all high remediated
Acceptance Testing	Validate against real-world scenarios with partners	Production-like	Manual + automated	Historical events passed; operator sign-off

5.2 Black Box Test Cases

Black box testing validates functionality without knowledge of internal implementation using equivalence partitioning, boundary value analysis, decision tables, and state transitions.

TC ID	Feature	Input	Expected Output	Technique
BB-01	Debris catalog search	Query: size>10cm AND altitude<1000km	Matching objects sorted by risk score	Equivalence partitioning
BB-02	Conjunction alert	Miss distance<100m, TCA<72hrs, Pc>1e-4	CDM generated; alert sent within 1 sec	Boundary value analysis
BB-03	Maneuver	LEO satellite,	Optimal delta-v	Decision table

	recommendation	Pc=2.5e-4	(0.05 m/s), timing, fuel cost	testing
BB-04	API rate limiting	1001 requests/min from single API key	HTTP 429 with Retry-After header	State transition testing
BB-05	Re-entry prediction	Perigee=180km, BSTAR=0.001, solar max	Decay window 72hrs ±2 hours	Error guessing
BB-06	Multi-object screening	Catalog of 500,000 objects	Screening <5 min; Pc>1e-5 identified	Performance testing

5.3 White Box Test Cases

White box testing examines internal code structure to ensure all paths, branches, and conditions are exercised with specific coverage targets.

TC ID	Module	Code Path	Input	Coverage
WB-01	SGP4 Propagator	propagate() with near-circular orbit	ISS TLE, propagate 24 hours	Statement coverage: 100%
WB-02	Collision Probability	computeProbability() with Vrel=0	Two objects with Vrel=0.0 m/s	Branch coverage: zero-velocity check
WB-03	Covariance Propagation	propagateCovariance() 7-day gap	Initial sigma=100m, propagate 7 days	Path coverage: growth bounds
WB-04	Spatial Index	octree.insert() with duplicates	Same ECI coordinates as existing	Condition coverage: all booleans
WB-05	Alert Priority	prioritize() with multiple events	Pc=1e-3, 1e-4, 1e-5	Decision coverage: all outcomes
WB-06	Data Ingestion	validate() with malformed TLE	Incorrect checksum in line 1	Loop coverage: zero/one/multiple

5.4 Validation and System Testing Approach

Validation ensures the system meets stakeholder needs; system testing verifies end-to-end functionality under realistic conditions.

Validation Testing: Alpha Testing validates against historical events (Iridium-Cosmos 2009, Fengyun-1C 2007, Cosmos 1408 2021). Beta Testing involves 3-month operational trial with 3 satellite operators and 1 space agency. Regulatory Validation includes third-party audit of CCSDS, ITAR, and IADC compliance.

System Testing: Scenario-Based Testing simulates complete mission lifecycle. Chaos Engineering uses Litmus/Gremlin with 30% failure tolerance target. Longevity Testing runs 30-day continuous operation. Interoperability Testing validates Space-Track, ESA DISCOS, and partner API integrations.

6. METRICS AND QUALITY

Software metrics and quality assurance activities provide quantitative measures of system health and ensure the highest standards of reliability, maintainability, and performance.

6.1 Software Metrics

Software metrics are classified into design metrics, code metrics, and testing metrics with target values and measurement tools.

Category	Metric	Definition	Target	Measurement
Design	Cyclomatic Complexity	Number of linearly independent paths through a function	<10 per function	SonarQube, Lizard
Design	Coupling Between Objects (CBO)	Number of classes coupled to a given class	<5 per class	SonarQube
Design	Design Structure Quality Index (DSQI)	Weighted composite index of architectural quality	>0.8	Custom tool
Code	Code Coverage	Percentage of code exercised by automated tests	>90% unit, >80% integration	JaCoCo, Coverage.py
Code	Technical Debt Ratio	Time to fix code smells / total development time	<5%	SonarQube
Code	Mean Time Between Failures (MTBF)	Average time between system failures	>720 hours	Prometheus/Grafana
Testing	Defect Density	Defects per 1000 lines of code	<0.5	Jira
Testing	Test Effectiveness	Defects found in testing / total defects	>85%	Post-release analysis
Testing	Alert Accuracy	True positives / (True positives + False positives)	>95%	Production monitoring

6.2 Quality Assurance Activities

Quality assurance activities are systematic processes ensuring the SDTMS meets specified requirements throughout the development lifecycle.

Activity	Description	Frequency
Code Reviews	Peer review of all PRs: algorithm correctness, security, performance	Every PR

Static Analysis	SonarQube, ESLint, Bandit, PMD quality gates	Every build
Architecture Reviews	Service boundaries, data flow, technology choices	Quarterly
Threat Modeling	STRIDE: data integrity, availability, confidentiality	Per feature
Performance Benchmarking	Regression testing of propagation and screening	Weekly
Security Audits	Penetration testing, vulnerability scans, SIEM review	Annual/Quarterly
Compliance Audits	ITAR/EAR, CCSDS, IADC verification	Bi-annually

6.3 Review Techniques

Review techniques are structured methods for evaluating work products to identify defects and share knowledge.

Technique	Application	Participants	Formality
Fagan Inspection	Critical algorithms: SGP4, Pc computation, covariance propagation	Domain experts, senior devs, QA	Formal
Pair Programming	Complex features: mission planner, screening, ML integration	Two developers	Informal
Walkthroughs	UI/UX: 3D dashboard, alert templates, API documentation	Designers, users, frontend devs	Semi-formal
Technical Reviews	Architecture: database, messaging, cloud provider selection	Architects, tech leads	Formal
Audit Reviews	Compliance: ITAR, export controls, CCSDS standards	Compliance officers, legal, auditors	Formal

7. CONCLUSION

The Space Debris Tracking and Mitigation System (SDTMS) represents a comprehensive software engineering solution to one of the most critical challenges facing modern aerospace operations. With over 36,500 tracked objects and an estimated 130 million untrackable fragments in Earth orbit, the threat of collision-induced cascading failures (Kessler Syndrome) demands sophisticated, reliable, and scalable software systems.

This case study has presented a complete software engineering lifecycle for the SDTMS, encompassing:

- **Requirements Engineering:** Comprehensive identification of 12 functional requirements and 8 non-functional requirements through stakeholder analysis. The SRS document captures user needs, system behaviors, and interface specifications with full traceability.
- **System Modeling:** Complete UML diagrams including Use Case Diagram (6 actors, 6 use cases with include/extend relationships), Class Diagram (inheritance hierarchy with 5 entity classes, 1 value object, 4 service classes), Sequence Diagram (6 lifelines, 10 message flows for collision detection workflow), Context Model (system boundary with 4 external data sources, 4 external systems, 5 stakeholder categories), and Data Model (ER diagram with 10 entities, 7 relationships with cardinality constraints).
- **Design Engineering:** A hybrid microservices architecture with event-driven processing and CQRS pattern addresses scalability, resilience, and real-time requirements. The architecture supports 1 million tracked objects with 99.999% availability.
- **Process and Risk Management:** Agile Scrum with DevOps practices enables iterative development with continuous stakeholder feedback. The RMMM plan identifies and mitigates five critical risks including sensor failures, propagation accuracy degradation, and cybersecurity threats.
- **Testing Strategy:** Multi-phase testing from unit to acceptance ensures system correctness and reliability. Black box and white box test cases cover functional requirements and code paths with >90% coverage targets.
- **Metrics and Quality:** Quantitative metrics for design, code, and testing quality drive continuous improvement. Quality assurance activities including code reviews, static analysis, threat modeling, and compliance audits maintain the highest standards.

Key Innovations: The SDTMS design introduces several innovative elements including polyglot persistence optimized for different data types, GPU-accelerated orbit propagation for large catalogs, machine learning-enhanced debris detection, and blockchain-based catalog integrity verification. The event-driven architecture with Kafka enables sub-second alert propagation for imminent collision events, a critical capability for satellite operator decision-making.

Future Enhancements: The modular architecture supports planned enhancements including integration with next-generation space-based sensors (Space Fence, SST), quantum computing for conjunction probability optimization, autonomous maneuver

execution with ground operator oversight, and international data sharing protocols for global space situational awareness.

The SDTMS demonstrates how modern software engineering principles — microservices, event-driven architecture, domain-driven design, continuous delivery, and comprehensive quality assurance — can be applied to solve complex, safety-critical problems in the aerospace domain. The system's success will be measured not only in technical metrics but in the preservation of orbital space for future generations of satellite missions and human space exploration.

REFERENCES

- [1] Inter-Agency Space Debris Coordination Committee (IADC), 'IADC Space Debris Mitigation Guidelines,' IADC-02-01, Revision 1, September 2007.
- [2] Consultative Committee for Space Data Systems (CCSDS), 'Orbit Data Messages,' CCSDS 502.0-B-2, Blue Book, November 2009.
- [3] Consultative Committee for Space Data Systems (CCSDS), 'Conjunction Data Message,' CCSDS 508.0-B-1, Blue Book, March 2013.
- [4] Vallado, D.A., 'Fundamentals of Astrodynamics and Applications,' 4th Edition, Microcosm Press, 2013.
- [5] Kessler, D.J. and Cour-Palais, B.G., 'Collision Frequency of Artificial Satellites: The Creation of a Debris Belt,' Journal of Geophysical Research, Vol. 83, No. A6, pp. 2637-2646, 1978.
- [6] European Space Agency (ESA), 'ESA's Annual Space Environment Report,' GEN-DB-LOG-00288-OPS-SD, 2024.
- [7] NASA Orbital Debris Program Office, 'Orbital Debris Quarterly News,' Volume 28, Issue 1, January 2024.
- [8] Alfano, S., 'A Numerical Implementation of spherical Object Collision Probability,' Journal of Astronautical Sciences, Vol. 53, No. 1, pp. 103-109, 2005.
- [9] Hoots, F.R. and Roehrich, R.L., 'Spacetrack Report No. 3: Models for Propagation of NORAD Element Sets,' December 1980.
- [10] Newman, L.K., et al., 'NASA's Conjunction Assessment Risk Analysis Process,' AAS 14-267, 2014.
- [11] United Nations Office for Outer Space Affairs (UNOOSA), 'Space Debris Mitigation Guidelines of the Committee on the Peaceful Uses of Outer Space,' A/62/20, 2007.
- [12] Newman, M., 'Building Microservices: Designing Fine-Grained Systems,' O'Reilly Media, 2nd Edition, 2021.
- [13] Hohmann, M., 'Domain-Driven Design: Tackling Complexity in the Heart of Software,' Addison-Wesley, 2003.
- [14] Pressman, R.S. and Maxim, B.R., 'Software Engineering: A Practitioner's Approach,' 9th Edition, McGraw-Hill Education, 2019.
- [15] Sommerville, I., 'Software Engineering,' 10th Edition, Pearson Education, 2016.
- [16] NRLMSISE-00 Empirical Model of the Atmosphere, Naval Research Laboratory, 2000.
- [17] Bowman, B.R., et al., 'A Method for Computing Accurate Daily Atmospheric Density Values from Satellite Drag Data,' AAS 04-172, 2004.

[18] Space-Track.org, 'Space Track Data Access,' <https://www.space-track.org>, accessed 2025.

[19] European Space Agency, 'DISCOS Database,' <https://discosweb.esoc.esa.int>, accessed 2025.

[20] ISO/IEC 25010:2011, 'Systems and Software Engineering — Systems and Software Quality Requirements and Evaluation (SQuaRE),' International Organization for Standardization, 2011.

Submitted by:

K. BISHWAS

Roll No: 25RBAIM0016

B.Tech. CSE (AI&ML) – I Year II Semester

MNR University, Hyderabad

SOFTWARE CRAFTING & SCULPTING

SPACE DEBRIS TRACKING & MITIGATION SYSTEM

Mini Case Study & Prototype Design

NAME: K.BISHWAS
ROLL NO:25RBAIM0016
SECTION: "A"
BRANCH : CSE AI&ML

End-to-End Engineering Analysis | Requirements • Architecture • Testing • Quality

SDTMS PROTOTYPE DESIGN

TABLE OF

CONTENTS

A comprehensive software engineering case study study covering requirements, system modeling, design design architecture, process management, testing, and testing, and quality assurance.

01 Requirements Engineering


02 System Modeling

03 Design Engineering

04 Process & Risk Management

05 Testing Strategy

06 Metrics & Quality Assurance



01

REQUIREMENTS ENGINEERING

Defining the functional scope, stakeholder needs, and system boundaries for the SDTMS

SDTMS platform

12 Functional Requirements — Core System Capabilities

 FR-01 Debris Detection & Tracking HIGH Multi-source sensor fusion (radar, optical, satellite) for debris >1cm in LEO	FR-02 Orbit Propagation & Prediction HIGH SGP4/SDP4 propagation with perturbation modeling (drag, SRP, J2)	 FR-03 Conjunction Analysis HIGH Collision probability assessment and CDM generation
 FR-04 Collision Avoidance Planning HIGH Optimal delta-v and timing recommendations for satellite operators	 FR-05 Mitigation Strategy Engine MED Laser ablation, drag sails, ADR missions, graveyard orbits	 FR-06 Real-time Alert System HIGH Collision warnings, re-entry alerts, breakup notifications
 FR-07 Debris Catalog Management HIGH Authoritative database with metadata, decay prediction	 FR-08 Visualization & Analytics MED 3D debris field, density heatmaps, temporal evolution	 FR-09 API Gateway MED REST/GraphQL APIs for operators, agencies, researchers
 FR-10 Mission Planning Support MED Low-debris-risk orbital insertions, EOL disposal	 FR-11 Regulatory Compliance LOW IADC/UN guidelines, 25-year rule, passivation	 FR-12 ML Enhancement MED Debris detection, anomaly detection, prediction

8 Non-Functional Requirements — Engineering Standards

Category	Requirement	Target Metric
Performance	Process object updates; conjunction screening; orbit propagation	> 100K updates/sec; < 5min screening; < 100ms propagation
Scalability	Horizontal scaling for tracked objects and API users	1M+ tracked objects; 500+ concurrent API users
Availability	Mission-critical uptime with zero-downtime deployments	99.999% uptime; automatic failover
Accuracy	Orbital position accuracy and collision probability confidence	< 100m position accuracy; > 95% Pc confidence
Security	End-to-end encryption, RBAC, ITAR/EAR compliance	mTLS, HashiCorp Vault, audit logging
Interoperability	CCSDS standards, TLE/OMM formats, external interfaces	Space-Track.org, ESA DISCOS, JSPOC integration
Real-time	Sub-second alert propagation for imminent collision events	< 1s for TCA < 72hrs; event-driven Kafka streams
Maintainability	Modular architecture, documentation, automated CI/CD	Microservices; OpenAPI; > 80% test coverage

SRS — Stakeholders & Interface Specifications

STAKEHOLDERS

-  **Satellite Operators** — Collision warnings, maneuver recommendations, fleet management APIs
-  **Space Agencies** (ISRO, NASA, ESA) — Global situational awareness, compliance monitoring
-  **Launch Providers** (SpaceX, ISRO, ULA) — Launch window risk assessment
-  **Insurance Companies** — Risk quantification, predictive analytics for premiums
-  **Research Institutions** — Open data access, debris population models
-  **Military/Defense** — Classified object tracking, ASAT threat detection

INTERFACE SPECIFICATIONS

Interface	Protocol	Format	Purpose
Sensor Ingestion	TCP/UDP, Kafka	Binary, XML	Raw radar, FITS
External Catalogs	HTTPS REST	JSON, XML	Space-Track TLEs
User Dashboard	WebSocket	JSON, Protobuf	Real-time 3D viz
API Gateway	HTTPS REST/GraphQL	JSON, XML	3rd-party integrations
Alert Notifications	SMTP, SMS, Webhook	Email, JSON	Collision warnings
ML Pipeline	gRPC	TF SavedModel	Model serving

02

SYSTEM MODELING

UML-based system representation: Use cases, class structures, behavioral sequences, and data sequences, and data relationships

Use Case & Context Model — Stakeholder Interactions

PRIMARY ACTORS

 **Satellite Operator**
Fleet management, alerts

 **Space Agency**
Global awareness, policy


 **Launch Provider**
Risk assessment

Sensor Network
Raw observation data

 **Research Institute**
Open data access

 **Insurance Company**
Risk quantification

SYSTEM CONTEXT MODEL



EXTERNAL SYSTEMS & DATA SOURCES

Space-Track.org TLE catalog

ESA DISCOS Debris data

JSPOC / UNOOSA Coordination

Ground Radar Eglin, Fylingdales


Optical Telescopes GEODSS, EOS

Space-Based Sensors SBSS, Sapphire


CORE USE CASES

- 1. Track & Catalog Debris
 - 2. Predict Collisions
 - 3. Generate Alerts
 - 4. Plan Mitigation
 - 5. Visualize Analytics
 - 6. Manage APIs
- «include» Orbit Propagation / «extend» Alert if $P_c > 1e-4$*


Class Architecture — Domain Model & Relationships



Collision Detection Sequence — Alert Workflow



Data Model — Entity-Relationship Architecture




■ Central Entity ■ Event/Alert Entities ■ Supporting Entities | 10 core entities, 8 relationships


03

DESIGN ENGINEERING

System architecture, design patterns, and quality attribute strategies for mission-critical critical operations



Hybrid Microservices Architecture — Event-Driven at Scale



Pattern: Event-Driven Microservices with CQRS — independent scaling, resilience via service isolation, sub-second alert propagation via Kafka streams

8 Design Quality Attributes — Mission Critical Engineering

Scalability

HPA, Kafka partitioning by object ID, read replicas for time-series DB

Availability

Multi-AZ deployment, circuit breakers (Resilience4j), graceful degradation

Maintainability

DDD bounded contexts, OpenAPI docs, automated testing >80% coverage

Performance

GPU acceleration for ML, pre-computed ephemerides, kd-tree spatial indexing

Security

Zero-trust architecture, mTLS between services, HashiCorp Vault, ITAR handling

Interoperability

CCSDS standards, TLE/OMM/JSON formats, STK-compatible output

Extensibility

Plugin architecture for new propagators, alert channels, screening thresholds

Real-time

Sub-second alert propagation via Kafka streams for TCA <72hrs events

Architectural Pattern Justification — Event-Driven Microservices with CQRS:

- **Scalability:** Independent scaling of compute-intensive services (orbit propagation, conjunction screening) via Kubernetes HPA
- **Resilience:** Service isolation prevents cascading failures; event replay enables recovery from any point
- **Real-time Processing:** Kafka streams enable sub-second alert propagation for urgent conjunctions
- **Data Consistency:** Event sourcing ensures complete audit trail for all orbital state changes
- **Flexibility:** Easy to add new sensor types, mitigation strategies, or ML models without disrupting existing services

04

PROCESS & RISK MANAGEMENT

Agile development methodology, sprint planning, and comprehensive risk mitigation strategies

Agile with DevOps — 2-Week Sprint Structure



WHY AGILE OVER WATERFALL?


 **Requirements Volatility** — Space situational awareness evolves rapidly (new sensors, regulations, ASAT threats). Agile accommodates change.

 **Algorithmic Complexity** — Orbit mechanics and collision probability require iterative refinement and continuous validation against real data.

 **Multi-Stakeholder Collaboration** — International agencies, operators, and researchers need frequent feedback loops via sprint reviews.

 **Compliance via DoD** — Regulatory requirements (ITAR, CCSDS) managed through Definition of Done checklists in each sprint.

SPR STRUCTURE



Risk Management — 5 Critical Risks with Mitigation

ID	Risk	Prob.	Impact	Mitigation Strategy	Management Plan
R-01	Sensor Data Ingestion Failure	Medium	Critical	Redundant sensor networks; international data sharing; SAR backup	Activate backup sources; interpolate orbits; notify operators of degraded accuracy
R-02	Propagation Accuracy Loss	High	Critical	Ensemble propagation; ML density corrections; increased update frequency	Switch to high-fidelity numerical propagation; issue uncertainty warnings
R-03	False Positives/Negatives	Medium	Critical	Multi-method Pc computation; covariance realism; ML risk scoring	Dynamic threshold tuning; operator feedback loop; A/B test on historical data
R-04	Cyberattack / Data Tampering	Low	Critical	Blockchain catalog integrity; anomaly detection; air-gapped critical systems	Catalog freeze and audit; fallback to verified backup; incident response activation
R-05	Regulatory Non-Compliance	Medium	High	Automated compliance in CI/CD; dedicated compliance officer; third-party audits	Suspend non-compliant features; legal review; remediation sprint; stakeholder notification

05

TESTING STRATEGY

Comprehensive test planning from unit testing through system validation for safety-critical operations

Test Plan — 6-Phase Testing Strategy

Phase	Objective	Environment	Tools	Exit Criteria
Unit Testing	Verify individual functions: SGP4 propagation, Pc computation, coordinate transforms	Local dev	Jest, pytest, JUnit	> 90% code coverage
Integration	Verify service interactions: ingestion → propagation → screening → alerts	Docker Compose	TestContainers, Postman	Kafka topics process correctly
System Testing	End-to-end workflow validation with simulated sensor data	Staging (K8s)	Selenium, k6	99.9% alert accuracy; < 5min latency
Performance	Validate scalability: 1M objects, 500 concurrent users	Performance env	Locust, JMeter	> 100K updates/sec; p99 < 100ms
Security	Identify vulnerabilities: OWASP Top 10, penetration testing	Isolated env	OWASP ZAP, Burp Suite	Zero critical vulnerabilities
Acceptance	Validate against real-world scenarios with space agency partners	Production-like	Manual + automated	Historical events validated

Black Box & White Box — 12 Test Cases

BLACK BOX TEST CASES

ID	Feature	Input	Technique
BB-01	Debris catalog search	size > 10cm AND altitude < 1000km	Equivalence partitioning
BB-02	Conjunction alert	missDist < 100m, TCA < 72hrs	Boundary value analysis
BB-03	Maneuver recommendation	LEO satellite, Pc > 1e-4	Decision table testing
BB-04	API rate limiting	1001 req/min from single key	State transition testing
BB-05	Re-entry prediction	perigee < 200km, high drag	Error guessing
BB-06	Multi-object screening	500,000 object catalog	Performance testing

WHITE BOX TEST CASES

ID	Module	Code Path	Coverage
WB-01	SGP4 Propagator	propagate() near-circular orbit	Statement coverage
WB-02	Pc Computation	computeProbability() Vrel ≈ 0	Branch coverage
WB-03	Covariance Propagation	propagateCovariance() 7-day gap	Path coverage
WB-04	Spatial Index	octree.insert() duplicate position	Condition coverage
WB-05	Alert Priority	prioritize() 3 urgent events	Decision coverage
WB-06	Data Ingestion	validate() malformed TLE	Loop coverage

COVERAGE TARGETS



Testing Techniques Applied:

- **Equivalence Partitioning** — reduces infinite input space to finite test classes
- **Boundary Value Analysis** — errors occur at boundaries (thresholds)
- **Decision Table Testing** — captures complex business rule combinations
- **Error Guessing** — leverages tester experience for defect-prone areas
- **Path/Branch/Statement Coverage** — structural coverage metrics

Validation & System Testing — Historical Event Correlation

VALIDATION APPROACHES

1 Alpha Testing

Internal validation against known historical conjunctions: **Iridium 33–Cosmos 2251** (2009) and **Fengyun-1C breakup** (2007). Verify system correctly predicts documented collision events.

2 Beta Testing

Partner with **3 satellite operators** and **1 space agency** for 3-month operational trial. Real-world usage feedback drives final adjustments before full deployment.

3 Regulatory Validation

Third-party audit of **CCSDS 508.0-B-1 compliance** for CDM generation, ITAR/EAR data handling verification, and IADC space debris mitigation guideline adherence.

SYSTEM TESTING METHODS



Scenario-Based Testing

Simulate complete mission lifecycle from launch injection through operational orbit to end-of-life disposal



Chaos Engineering

Randomly terminate services using Litmus/Gremlin to test resilience, failover mechanisms, and graceful degradation



Longevity Testing

30-day continuous operation with synthetic data to detect memory leaks, performance degradation, and resource exhaustion




Interoperability Testing

Validate data exchange with Space-Track.org and ESA DISCOS using real APIs to ensure CCSDS compliance

06

METRICS & QUALITY

Quantifiable engineering metrics, quality assurance activities, and review techniques



Software Metrics — 9 KPIs Across 3 Categories

DESIGN METRICS	CODE METRICS	TESTING METRICS
<10 Cyclomatic Complexity per function (SonarQube)	>90% Code Coverage (Unit) >80% integration (JaCoCo)	<0.5 Defect Density per 1000 LOC (Jira)
<5 Coupling Between Objects per class (SonarQube)	<5% Technical Debt Ratio fix time / dev time (SonarQube)	>85% Test Effectiveness defects found / total defects
>0.8 Design Structure Quality Index (DSQI, custom tool)	>720h Mean Time Between Failures (Prometheus/Grafana)	>95% Alert Accuracy TP / (TP + FP) production

MEASUREMENT TOOLS

Static Analysis: SonarQube (complexity, CBO, debt ratio), Lizard (complexity), ESLint (JS), Bandit (Python security)

Coverage: JaCoCo (Java), Coverage.py (Python), integrated into CI/CD pipeline with quality gates

Monitoring: Prometheus + Grafana for MTBF, alert accuracy, system throughput; Jira for defect tracking

Custom: DSQI calculator for architectural quality; alert correlation engine for accuracy measurement

Quality Assurance — Activities & Review Techniques

QA ACTIVITIES



Code Reviews — Peer review of all PRs; focus on algorithm correctness, security, performance
Frequency: Every PR | Tool: GitHub/GitLab



Static Analysis — SonarQube, ESLint, Bandit; enforce quality gates in CI/CD
Frequency: Every build | Tools: SonarQube, ESLint, Bandit



Architecture Reviews — Quarterly review of service boundaries, data flow, tech choices
Frequency: Quarterly | Participants: Architects, Tech Leads



Threat Modeling — STRIDE-based analysis for new features; focus on data integrity
Frequency: Per feature | Method: STRIDE



Performance Benchmarking — Automated regression of propagation and screening
Frequency: Weekly | Tools: Custom benchmarks



Security Audits — Annual third-party penetration testing; quarterly vulnerability scans
Frequency: Annual/Quarterly | Tools: Pen test, OWASP ZAP



Compliance Audits — ITAR/EAR data handling, CCSDS standard compliance review
Frequency: Bi-annually | Scope: ITAR, CCSDS, IADC

REVIEW TECHNIQUES

1 Fagan Inspection

For critical algorithms: SGP4 implementation, Pc computation. Participants: domain experts, developers, testers.

2 Pair Programming

For complex features: mitigation mission planner. Two developers collaborate in real-time on design and implementation.

3 Walkthroughs

For UI/UX design of 3D visualization dashboard. Participants: designers, end-users, developers. Informal, discussion-driven.

4 Technical Reviews

For architecture decisions: database selection, messaging system. Participants: architects, tech leads. Decision-focused.

5 Audit Reviews

For regulatory compliance: ITAR, export controls. Participants: compliance officers, legal, security. Formal audit trail.

SPACE DEBRIS TRACKING & MITIGATION SYSTEM

KEY INNOVATIONS & TAKEAWAYS



Real-world Complexity

Genuine cutting-edge challenges in orbital mechanics and international coordination



Multi-disciplinary

Astrodynamics, distributed systems, machine learning, and regulatory compliance



Scalability Focus

Designed for 1M+ tracked objects with sub-second alert latency



Safety-Critical Rigor

99.999% availability, fault tolerance, and regulatory compliance for space operations

"Preserving the space environment for future generations."

Thank you for your attention

SOFTWARE ENGINEERING CASE STUDY